



62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93

**EXTRA AREA**

Bellview Road	9	Sq. Yds.
E. 296 <sup>th</sup> Street	6	Sq. Yds.
E. 297 <sup>th</sup> Street	5	Sq. Yds.
E. 298 <sup>th</sup> Street	6	Sq. Yds.
E. 299 <sup>th</sup> Street	17	Sq. Yds.
Worden Road	30	Sq. Yds.
E. 300 <sup>th</sup> Street (N)	11	Sq. Yds.
E. 300 <sup>th</sup> Street (S)	67	Sq. Yds.
<b>Total</b>	<b>211</b>	<b>Sq. Yds.</b>

**WATER**

Water Manholes castings adjusted to grade	2	Each
Valve Boxes adjusted to grade	2	Each

**SURFACE - REMOVAL & DISPOSAL**

Extra Area	211	Sq. Yds.
Sta. 62+00 to Sta. 93+00 = 3100' x 8' = 24,800 Sq. Ft. ÷ 9 =	2735.55	Sq. Yds.
* Sta. 62+00 to Sta. 93+00 = 3100' x 32' = 99,200 Sq. Ft. ÷ 9 = 11,022.22 x 2%	220.44	Sq. Yds.
<b>Total</b>	<b>3186.99</b>	<b>Sq. Yds.</b>

\* Note: - Surface Course in this area to be removed as directed by the Engineer

**SEWERS**

Catchbasin Casting adjusted to grade	11	Each
Storm Manhole adjusted to grade	3	Each
Sanitary Manhole adjusted to grade	5	Each