FED. RD. DIST. NO.	STATE	FED. AID PROJECT	FISCAL YEAR
10	OHIO	5A(5)	1941

39
43

LAKE COUNTY
S.H. 2 SEC. Q(Pt)

Tree Protection (DUAL TYPE)

Station	Side	Size	Kind	Rip-Rap Wells & Aeration: Wells: Semi Cir. Dia.	Wells: Average Height	Wells: Sq. Yd.	Aeration: Inches Average Depth	Aeration: Rect-angular	Aeration: Total Cu. Yds.	Pruning Exist. Trees: Pay Size 6"	12"	20"	30"	36"	Berm Steepened At Tree Etc.
567+17	L	45"	Elm											1	
572+4	L	34"	Maple										1		
572+48	L	50"	Maple											1	
575+13	R	74"	Maple				2"	12'x40'	2.96						
575+83	R	57"	Maple				3"	12'x40	4.44						
576+48	R	56"	Maple				3"	12'x40	4.44						
584+64	R	48"	Maple				2"	10'x30	1.85					1	
584+80	R	35"	Maple				2"	10'x28'	1.73				1		
585+12	R	52"	Maple				2"	8'x40'	1.98						
587+30	R	56"	Maple				2"	12'x40'	2.96						
596+70	R	10"	Plum				3"	12'x20'	2.22						
597+51	R	36"	Maple				3"	12'x30	3.33					1	
609+48	L	74"	Maple											1	
613+19	L	36"	Elm				3"	6'x30'	1.67						
613+44	L	26"	Pignut				3"	6'x25'	1.39						
620+46	L	50"	Oak				3"	16x40'	5.93						
631+49	L	67"	Maple											1	
632+01	L	63"	Maple											1	
633+79	L	57"	Maple											1	
637+11	L	34"	Maple				2"	10'x20'	1.23						
637+98	L	29"	Maple				3"	10"x30'	2.78						
639+50	L	14"	Oak				2"	8'x20'	0.99		1				
639+70	L	12"	Oak				2"	8'x30'	1.48		1				
639+92	L	43"	Triple Oak				3"	11'x40'	4.07					1	
640+35	L	29"	Oak										1		
640+36	L	17"	Oak									1			
640+38	L	27"	Oak										1		
640+39	L	17"	Oak				3"	12X70'	7.78			1			
640+55	L	18"	Oak									1			
640+59	L	10"	Oak								1				
640+65	L	10"	Oak								1				
641+13	L	30"	Twin Oak												
641+18	L	22"	Oak												
641+23	L	10"	Oak												
641+33	L	15"	Oak								1				
641+44	L	19"	Oak									1			
641+52	L	23"	Oak									1			
641+74	L	27"	Oak				3"	12'x142'	15.78						
641+78	L	13"	Oak												
641+90	L	18"	Oak												
642+05	L	17"	Oak												
642+12	L	14"	Oak												
642+22	L	16"	Oak												
642+27	L	17"	Oak												
642+73	L	24"	Oak				3"	12'x34'	3.78				1		
642+77	L	29"	Oak												
643+53	L	16"	Oak												
643+73	L	21"	Oak				3"	12'x60'	6.67						
643+82	L	21"	Oak									1			
675+10	L	26"	Apple	10'	1.5	2.62	3"	15'x25	3.47				1		
678+73	L	14"	Weeping Birch				3"	12'x20'	2.22		1				
678+96	L	22"	Walnut									1			
679+28	L	28"	Maple				3"	12'x20'	2.22						
679+97	L	28"	Maple										1		
680+33	L	30"	Maple										1		
680+65	L	13"	Maple								1				
680+99	L	29"	Maple										1		
681+33	L	33"	Maple				2"	11'x220	14.94				1		
681+66	L	39"	Maple											1	
681+98	L	33"	Maple										1		
682+30	L	33"	Maple										1		
					Total	2.62			102.31		7	7	12	10	