

GENERAL SUMMARY

ITEM	SHEET NUMBER															ITEM	ITEM EXT.	TOTAL HE S-69(103) FUNDING	UNIT	DESCRIPTION
	4	6	7	9	10	11	12	13	14	15										
																				ROADWAY
201				LUMP												201	11000	LUMP		CLEARING & GRUBBING
202											54	20				202	23000	74	SQ. YD.	PAVEMENT REMOVED
202											14					202	30800	14	SQ. YD.	TRAFFIC ISLAND REMOVED
202								124	350		353	15	150			202	32000	992	LIN. FT.	CURB REMOVED
202											76	125				202	32501	201	LIN. FT.	CURB AND GUTTER REMOVED, AS PER PLAN (SEE SHT 4)
202													42			202	35100	42	LIN. FT.	PIPE REMOVED, 24" AND UNDER
202																202	58100	1	EACH	CATCH BASIN REMOVED
202																202	58200	1	EACH	INLET REMOVED
202								69	447		385	68	198	222		203	12000	1389	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION
202											57		55	395		203	20000	507	CU. YD.	EMBANKMENT
202								2284								203	50000	2284	SQ. YD.	SUBGRADE COMPACTION
606																606	13000	325	LIN. FT.	GUARDRAIL, TYPE 5
606																606	25000	3	EACH	ANCHOR ASSEMBLY, TYPE A
606																606	26500	5	EACH	ANCHOR ASSEMBLY, TYPE T
608								1								608	50000	3	EACH	CURB RAMP, TYPE 1
608																608	54000	25	SQ. FT.	CURB RAMP, TYPE 2
																				EROSION CONTROL
207																207	70000	100	EACH	STRAW OR HAY BALES
659																659	10000	2994	SQ. YD.	SEEDING AND MULCHING
659																659	20000	0.28	TON	COMMERCIAL FERTILIZER
659																659	30000	1.4	TON	AGRICULTURAL LIMING
659																659	35000	7	M. GAL.	WATER
																				DRAINAGE
603																603	04400	15	LIN. FT.	12" CONDUIT, TYPE B, 706.02 OR 706.08 WITH CLASS A BEDDING
603																603	04400	65	LIN. FT.	12" CONDUIT, TYPE B, 706.02 OR 706.08
603																603	04600	35	LIN. FT.	12" CONDUIT, TYPE C, 706.02 OR 706.08
604																604	00401	2	EACH	CATCH BASIN, No. 3, AS PER PLAN (SEE SHT 4)
604																604	18301	1	EACH	INLET, 2-A-10, AS PER PLAN (SEE SHT 4)
604																604	34500	4	EACH	MANHOLE ADJUSTED TO GRADE