

GENERAL SUMMARY

CALC. BY JC
DATE 2-89
CHKD. BY LME
DATE 1-25-91

LAKE COUNTY
LAK - 20 - 3.26

OHIO
FHWA REGION 5

8A
36

*100% CITY PARTICIPATION

ITEM	SHEET NUMBER													ITEM	ITEM EXT.	TOTAL HES-69(103) FUNDING	UNIT	DESCRIPTION
	4	6	7	9	11	12	13											
																		WATERWORK
SPECIAL															* 1		EACH	6" HYDRANT ASSEMBLY, TYPE A
SPECIAL															* 1		EACH	HYDRANT EXTENDED AND ADJUSTED TO GRADE
SPECIAL															1		EACH	HYDRANT REMOVED FOR STORAGE
SPECIAL																	EACH	VALVE BOX ADJUSTED TO GRADE
SPECIAL															500		POUND	MISCELLANEOUS METAL WORK
202															1		EACH	ABANDONED, MISC. METER VAULT
																		PAVEMENT
301															557		CU. YD.	BITUMINOUS AGGREGATE BASE, AC-20
304															407		CU. YD.	AGGREGATE BASE, AS PER PLAN (SEE SHT. 4)
402															115		CU. YD.	ASPHALT CONCRETE, AC-20
404															82		CU. YD.	ASPHALT CONCRETE, AC-20
404															1		CU. YD.	ASPHALT CONCRETE, AC-20 (DRIVEWAYS)
452															18		SQ. YD.	8" PLAIN CONCRETE PAVEMENT
609															1137		LIN. FT.	CURB, TYPE 6
612															1		SQ. YD.	6" CONCRETE TRAFFIC ISLAND
																		TRAFFIC CONTROL (FOR QUANTITIES SEE SHEETS 25 & 26)
																		MAINTENANCE OF TRAFFIC
404															50		CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC
410															50		CU. YD.	TRAFFIC COMPACTED SURFACE TYPE A OR B
614															.78		MILE	TEMPORARY LANE LINE, CLASS I
614															.36		MILE	TEMPORARY CENTER LINE, CLASS I
614															.07		MILE	TEMPORARY EDGE LINE, CLASS I
614															1480		LIN. FT.	TEMPORARY CHANNELIZING LINE, CLASS I
614															343		LIN. FT.	TEMPORARY STOP LINE, CLASS I
614															537		LIN. FT.	TEMPORARY CROSSWALK LINE, CLASS I
614															23		EACH	TEMPORARY LANE ARROW, CLASS I
616															1		TON	CALCIUM CHLORIDE
616															4		M GAL	WATER
614																		MAINTAINING TRAFFIC (PARTS 1&2)
619																		FIELD OFFICE, TYPE B (PARTS 1&2)
619																		CONSTRUCTION LAYOUT STAKES, AS PER PLAN (PART 1)
623																		CONSTRUCTION LAYOUT STAKES (PART 2)
624																		MOBILIZATION (PARTS 1&2)