SIGNS TO BE ERECTED

ITEM 630

SHEET NO.	STATION	OFFSET	SIDE L.-OR-R.	SIGNS, FLAT SHEET R-31C-48 SQ. FT.	SIGNS, FLAT SHEET R-32R-30 SQ. FT.	SIGNS, FLAT SHEET R-31B-36 SQ. FT.	SIGNS, FLAT SHEET TYPE G R-26A-30 SQ. FT.	R-30A-30 SQ. FT.	R-27A-30 SQ. FT.	R-26A-36 SQ. FT.	R-30A-36 SQ. FT.	R-27A-36 SQ. FT.	R-25E(L)-24 SQ. FT.	GROUND MOUNTED SUPPORT No. OF POSTS REQ'D. EACH	GROUND MOUNTED SUPPORT NO.3 POST LIN.FT.	SIGN SUPPORT ASSEMBLY, POLE MOUNTED EACH	SIGN HANGER ASSEMBLY, SPAN WIRE EACH
28			ON WIRE										5.0				1
31	6+25	36'	R	10.0										2	13/13		
31	8+15	43'	R	10.0										2	13/13		
31	9+85	51'	L		6.25									1	13		
31	11+80	50'	L		6.25									1	13		
31	12+20	47'	L				7.5	15.0	7.5								
31	13+00	30'	R	10.0										2	13/13		
32	15+30	71'	L			7.5								2	13/13		
32	15+33	26'	R	10.0										2	13/13		
32	16+05	49'	L		6.25									1	13		
32	16+75	48'	L				7.5	15.0	7.5								
33	199+00	38'	R	10.0										2	13/13		
33	200+35	42'	R	10.0										2	13/13		
33	201+40	56'	L		6.25									1	13		
33	203+35	63'	L		6.25											1	
33	203+35		R&L							21.0	21.0	10.5					
SUBTOTAL				60.0	31.25	7.5	15.0	30.0	15.0	21.0	21.0	10.5	5.0		234	1	1
TOTAL				98.75			117.5								234	1	1

ITEM 630 REMOVAL OF GROUND MOUNTED SIGN AND STORAGE, AS PER PLAN AND ITEM 630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND STORAGE, AS PER PLAN.

SHEET NO.	STATION	OFFSET	SIDE L.-OR-R.	SIGN EACH	GROUND MOUNTED POST EACH
31	10+58.5	36'	L	1	1
31	13+24.5	32'	L	1	1
32	14+45.5	31'	L	1	1
32	17+80	27'	L	1	2
31	9+81	48'	L		1
32	15+05	32'	L		1
TOTAL				4	7

ITEM 630 REMOVAL OF GROUND MOUNTED SIGN AND REERECTION

SHEET NO.	STATION	OFFSET	SIDE L.-OR-R.	GROUND MOUNTED SUPPORT, No. 3 POST EACH	GROUND MOUNTED SUPPORT, No. 3 POST LIN.FT.
31	9+81	54'	L	2	13
32	15+05	48'	L	2	13
TOTAL				4	26

THESE TOTALS HAVE BEEN TRANSFERRED TO THE TRAFFIC CONTROL GENERAL SUMMARY, SEE SHEET No. 25.