CALC. BY DATE	LAK-20-7.30 AND VARIOUS	OHIO
CHKD. BY DATE		FHWA REGION
	F-69 (110) M-1099 (26)	FEDERAL PROJECT

ITEM 642 PAVEMENT MARKING QUANTITIES

SHEET Nº.	STATION FROM	STATION TO	LOCATION	SIDE RT.	SIDE LT.	EDGE LINES WHITE L.F.	EDGE LINES YELLOW L.F.	LANE LINES L.F.	CENTER LINES DOUBLE / SOLID L.F.	CENTER LINES DASHED / SOLID L.F.	CENTER LINES DASHED L.F.	CHANNELIZING LINES L.F.	STOP LINES L.F.	CROSSWALK LINES L.F.	TRANSVERSE WHITE L.F.	TRANSVERSE YELLOW L.F.	LANE ARROWS EA.	WORD ON PAVEMENT ONLY EA.	WORD ON PAVEMENT SCHOOL EA.	WORD ON PAVEMENT	DOTTED LINE WHITE L.F.	DOTTED LINE YELLOW L.F.
24	0+38	0+44	RAMP "V"	✓	✓									78								
"	0+48	0+50	"	✓									25									
"	0+80				✓												2					
25	9+25	9+67	FAIRFAX		✓								23									
"	9+71	9+77	"	✓	✓									108								
25	268+50	270+72	S.R. 615	✓					222													
"	269+30	270+72	"	✓								142										
"	269+04		"	✓													1					
"	270+04		"	✓														1				
"	270+42		"	✓													1					
"	270+78	270+80	"	✓									22									
"	271+77	271+94	"	✓	✓									84								
"	272+02	272+04	"		✓								24									
"	272+04	274+60	"	✓								256										
"	272+04	274+60	"	✓					256													
"	272+35		"	✓													1					
"	272+71		"	✓														1				
"	273+10		"	✓													1					
25	0+34	0+40	HIGH SCHOOL	✓	✓									138								
"	0+44	0+56	"		✓								34									
"	0+48		"		✓												2					
"	0+46	1+46	"	✓	✓				100													
"	0+46	1+46	"		✓							100										
26	285+38	287+82	S.R. 615	✓					270													
"	285+82	286+52	"	✓											55							
"	286+57	287+82	"	✓								125										
"	286+20	288+40	"	✓								130										
"	280+68		"	✓													1					
"	287+14		"	✓														1				
"	287+54		"	✓													1					
"	287+78		"	✓														1				
"	287+82	287+84	"	✓									11									
"	288+18	288+48	"	✓											88							
"	288+19		"	✓													1					
"	288+18	288+43	"	✓					50													
"	288+40	288+42	"	✓									23									
"	288+53	289+59	"	✓	✓									102								
"	289+53	289+55	"	✓	✓								24									
"	289+55	292+10	"	✓								855										
"	289+55	292+10		✓					255													
"	289+85		"	✓													1					
26	0+36	0+50	CIVIC	✓	✓									159								
"	0+50	0+52	"		✓								31									
"	0+52	0+65	"		✓				13													
"	0+52	1+00	"		✓							48										
27	165+28	168+25	JACKSON ST.	✓	✓				257													
"	168+25	168+27	"	✓									18									
"	169+43	169+45	"		✓								18									
"	169+45	171+93	"	✓	✓				248													
27	36+96	39+52	HEISLEY Rd.	✓	✓				256													
"	39+52	39+54	"	✓									11									

SHEET Nº.	STATION FROM	STATION TO	LOCATION	SIDE RT.	SIDE LT.	EDGE LINES WHITE L.F.	EDGE LINES YELLOW L.F.	LANE LINES L.F.	CENTER LINES DOUBLE / SOLID L.F.	CENTER LINES DASHED / SOLID L.F.	CENTER LINES DASHED L.F.	CHANNELIZING LINES L.F.	STOP LINES L.F.	CROSSWALK LINES L.F.	TRANSVERSE WHITE L.F.	TRANSVERSE YELLOW L.F.	LANE ARROWS EA.	WORD ON PAVEMENT ONLY EA.	WORD ON PAVEMENT SCHOOL EA.	WORD ON PAVEMENT	DOTTED LINE WHITE L.F.	DOTTED LINE YELLOW L.F.
27	40+29	40+31	HEISLEY Rd.		✓								23									
"	40+31	41+20	"		✓							89										
"	40+31	42+86	"	✓	✓				256													
"	40+34		"		✓												1					
"	40+36		"		✓												1					
"	40+74		"		✓													1				
"	41+17				✓												1					
28	712+08		S.R. 283	✓													1					
"	712+36	712+38	"	✓	✓								24									
"	712+43	712+62	"	✓	✓									88								
"	713+43	713+67	"	✓	✓									88								
"	713+71	713+73	"	✓	✓								21									
"	713+73	716+24	"	✓	✓				251													
"	709+90	712+36		✓	✓				246													
"	711+36	712+36										100										
"	711+70																	1				
28	0+44	0+46	CORDUROY RD.		✓								19									
"	0+46	2+10	"		✓							164										
"	0+68	0+70	"	✓	✓								12									
"	0+70	2+10	"	✓					140													
"	0+94		"		✓												1					
"	1+05		"		✓												1					
"	1+33		"		✓													1				
"	1+43		"		✓													1				

SHEET SUB-TOTAL M-1099(26)				2.820		1.459	345	845		137	18	8										
SUB-TOTAL FROM SHEET 44 (M-1099(26))	1,047	950	906	3,169		2.000	649	1,901	155	1,038	21	13					100					
SUB-TOTAL FROM SHEET 45 (F-69(110))			4,153	2,518	190	2,208	571	1,781			14	9										
SUB-TOTAL FROM SHEET 46 (M-1099(26))			4,672	2,929	496	2,182	664	1,895		485	22	7	2				92					
SUB-TOTAL FROM SHEET 46 (F-69(110))	1,047		860	320			40															
TOTAL ALL SHEETS M-1099 (26)		950	5,578	8,918	496	5,641	1683	4,641	155	1,660	61	24	2				192					
TOTAL ALL SHEETS F-69 (110)			5,013	2,938	190	2,448	611	1781			14	9										
GRAND TOTAL TO SHEET 4C	1,047	950	10,591	11,756	686	7,849	2,294	6,422	155	1,660	75	33	2				192					
	0.378	MILES	2.01 MI.	2.356 MILES																		

BRUNING 44-132 62820