

# INTERCONNECT QUANTITIES

CALC. BY:	LAK-20/84-0.39/1.24	OHIO
DATE:		FHWA REGION <b>5</b>
CHKD. BY:		FEDERAL PROJECT
DATE:		

43  
46

RIDGE RD. (S.R. 84) SYSTEM					
INTERSECTION	CONNECTION	POLE NO.	6 PAIR PE-39 QTY (IN FT.)	6 PAIR PE-38 QTY (IN FT.)	
RIDGE & BISHOP	CONTROLLER STA 09+90, 48'L		0		
	PULLBOX STA 09+92, 56'L		13		
	PULLBOX STA 10+39, 55'L		53		
	POLE 1	551179	128		
	POLE 1A	607239		153	
	POLE 2	220839		105	
	POLE 3	33138		91	
	POLE 4	356680		136	
	POLE 4A	296062		116	
	POLE 5	NO NUMBER		151	
	POLE 6	296065		152	
	POLE 7	296066		153	
	POLE 7A	336797		134	
	POLE 8	359512		108	
POLE 9	269069		144		
	PULLBOX STA 25+20, 21'L		33		
	PULLBOX STA 25+79, 22'L		64		
	PULLBOX STA 25+94, 19'R		52		
RIDGE & E. 290th	CONTROLLER STA 25+83, 37'R		48		
	PULLBOX STA 25+94, 19'R		28		
	PULLBOX STA 25+79, 22'L		48		
	POLE 10	247116	52		
	POLE 11	NO NUMBER		118	
	POLE 12	296188		146	
	POLE 13	296187		121	
	POLE 14	296186		137	
	POLE 15	296185		131	
	POLE 16	296184		145	
	POLE 17	337367		144	
	POLE 18	296182		118	
	POLE 19	NO NUMBER		113	
		PULLBOX STA 37+78, 26'L		58	
	PULLBOX STA 38+19, 26'L		47		
RIDGE & LINCOLN	CONTROLLER STA 38+20, 44'L		21		
	PULLBOX STA 38+19, 26'L		21		
	POLE 20	321285	77		
	POLE 21	NO NUMBER		41	
	POLE 22	NO NUMBER		133	
	POLE 23	296178		128	
	POLE 24	296177		149	
	POLE 25	296176		114	
	POLE 26	296175		151	
	POLE 27	316213		134	
	POLE 28	304628		156	
		PULLBOX STA 48+05, 17'L		46	
		PULLBOX STA 49+02, 27'L		107	
		PULLBOX STA 49+29, 27'L		29	
	PULLBOX STA 49+72, 23'L		53		
	PULLBOX STA 49+62, 16'R		46		
RIDGE & ROCKEFELLER	CONTROLLER STA 49+44, 41'R		42		
TOTALS SHEET 43 (STP- )			1066	3622	
TOTALS FROM SHEET 42 (NH- )			2739	9183	
GRAND TOTAL SHEETS 42 & 43			3805	12805	