



TYPICAL SECTION
SCALE 1IN = 2 FT.

- QUANTITIES**
- 2,485 CU.YDS. EXCAVATION
 - 12,139 SQ.YDS. BRICK PAVEMENT
 - 12,778 SQ.YDS. 6" CONCRETE BASE
 - 11,500 LIN.FT. 6" INTEGRAL CONCRETE FLUSH CURB
 - 5,750 LIN.FT. 6" VIT. SEWER PIPE
 - 12,778 SQ.YDS. OLD BRICK REMOVED
 - 11,500 LIN.FT. 5"x15" STONE CURB REMOVED

All old brick & stone curb to be piled near the site of the improvement & to become the property of Lane County.