GENERAL SUMMARY

CALC. BY	TJH
DATE	7/93
CHKD. BY	SJS
DATE	7/93

LAK-283-3.83
PLAN 81

OHIO
FHWA REGION 5

SHEET NUMBER 7	8	8A	9	10	10A	15	15A	15B	17	18	74	75	77	78	MAINTE-NANCE FUNDS	BIKE-WAY FUNDS	ITEM	ITEM EXT.	TOTAL QTY.	UNIT	DESCRIPTION	AS PER PLAN SHT.#
																					MAINTENANCE OF TRAFFIC	
			50													50	404	35000	50	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
			350													350	410	22000	350	TON	TRAFFIC COMPACTED SURFACE, TYPE A OR B	
			9.2												9.2		614	21400	9.2	MILE	TEMPORARY CENTER LINE, CLASS II	
			916													916	614	23604	916	LIN.FT.	TEMPORARY CHANNELIZATION LINE, CLASS II	
			7													7	616	10000	7	M.GAL.	WATER	
			7													7	616	20000	7	TON	CALCIUM CHLORIDE	
																					TRAFFIC CONTROL	
													727			727	630	03100	727	LIN.FT.	GROUND MOUNTED SUPPORT, NO. 3 POST	
													5			5	630	08500	5	EACH	STREET NAME SIGN SUPPORT	
													199			199	630	80100	199	SQ.FT.	SIGN, FLAT SHEET	
													5			5	630	85000	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	
													24			24	630	85100	24	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
													21			21	630	86002	21	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
											70	10					625	25100	80	LIN.FT.	CONDUIT, 1", 713.04	
											754	88					632	27500	842	LIN.FT.	LOOP DETECTOR PAVEMENT CUTTING	
											803	106					632	64900	909	LIN.FT.	LOOP DETECTOR WIRE, TYPE E	
														10.886		10.886	642	00102	10.9	MILE	EDGE LINE, TYPE 2	
															2.632		642	00302	2.7	MILE	CENTER LINE, TYPE 2	
														974	974		642	00402	974	LIN.FT.	CHANNELIZING LINE, TYPE 2	
														392	392		642	00502	392	LIN.FT.	STOP LINE, TYPE 2	
														1132	722	410	642	00602	1,132	LIN.FT.	CROSSWALK LINE, TYPE 2	
														890	890		642	00702	890	LIN.FT.	TRANSVERSE LINE, TYPE 2	
														3378	3378		642	00902	3378	SQ.FT.	ISLAND MARKING, TYPE 2	
														2	2		642	01102	2	EACH	SCHOOL SYMBOL MARKING, 72" TYPE 2	
														9	9		642	01302	9	EACH	LANE ARROW, TYPE 2	
														4	4		642	01402	4	EACH	WORD ON PAVEMENT, 72", TYPE 2 "ONLY"	
														1076		1076	642	01512	1076	LIN.FT.	DOTTED LINE, 6", TYPE 2	
														62		62	642	50010	62	EACH	PAVEMENT MARKING MISC: PREFERENTIAL LANE MARKING, TYPE 2	
			LUMP												LUMP	LUMP	614	11000	LUMP	LUMP	MAINTAINING TRAFFIC	
			LUMP												LUMP	LUMP	619	15000	LUMP	LUMP	FIELD OFFICE, TYPE A	
			LUMP												LUMP	LUMP	623	10000	LUMP	LUMP	CONSTRUCTION LAYOUT STAKES	
			LUMP												LUMP	LUMP	624	10000	LUMP	LUMP	MOBILIZATION	

PR10520/GEN4.DWG 7/13/93