

I:\PROJECTS\PID19489\19489GNA.DGN 19-OCT-1999 10:36AM jgrmovse

ITEM 203 - LINEAR GRADING

THIS ITEM SHALL CONSIST OF EXCAVATING TOPSOIL, PLACING GRANULAR MATERIAL AND APPLYING HERBICIDE, ON BOTH SIDES OF THE ROAD, AND IN ACCORDANCE WITH THE FOLLOWING:

ALL COLLECTED DEBRIS AND TOPSOIL, INCLUDING RHIZOMES, ROOTS, AND OTHER VEGETATIVE PLANT MATERIAL SHALL BE REMOVED AND DISPOSED OF AS SPECIFIED IN SECTION 203.05 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS.

ANY REMOVAL OF THE ABOVE ITEMS WHICH EXTEND BELOW THE PROPOSED SUBGRADE SHALL BE REPLACED WITH COMPACTABLE GRANULAR MATERIAL CONFORMING TO 203.02 AND SHALL BE PLACED TO GRADE AS DETAILED ON THE TYPICAL SECTION OR AS APPROVED BY THE ENGINEER.

HERBICIDE SHALL BE TREFLAN E.C., SPIKE, OR AN APPROVED EQUAL AND SHALL BE APPLIED TO THE PREPARED AREA AFTER FINAL LEVELING AND GRADING HAS BEEN COMPLETED. THE APPLICATION SHALL BE JUST PRIOR TO PAVING AND SHALL STRICTLY ADHERE TO THE MANUFACTURER'S LABEL INSTRUCTIONS.

ONLY PROPERLY LICENSED PERSONNEL SHALL APPLY HERBICIDES AS REQUIRED BY THE OHIO REVISED CODE.

ALL EQUIPMENT, MATERIALS, AND LABOR REQUIRED TO PERFORM THE WORK OUTLINED ABOVE SHALL BE INCLUDED FOR PAYMENT UNDER ITEM 203-LINEAR GRADING.

THE FOLLOWING QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY:  
ITEM 203 - LINEAR GRADING 410 STA.

LOOP DETECTORS

AN ESTIMATED QUANTITY OF ITEM 632-DETECTOR LOOP HAS BEEN PROVIDED AS A CONTINGENCY WHEN WIRE IS CUT, BROKEN, OR DESTROYED DUE TO PAVEMENT REPAIR OR BUTT JOINT OPERATIONS.

NEW LOOP DETECTORS SHALL BE PLACED AT THE SAME LOCATIONS AND SAME SIZE AS THE EXISTING. THE LOOP DETECTOR WIRE SHALL BE REPLACED TO THE PULL BOX OR POLE, WHICHEVER IS APPLICABLE, UNDER ITEM 632 AND TC-82.10M.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY:

ITEM 632-DETECTOR LOOP 5 EACH

ITEM 251 - PARTIAL DEPTH PAVEMENT REPAIR:

AN ESTIMATED QUANTITY HAS BEEN PROVIDED AND SHALL BE USED AS DIRECTED BY THE ENGINEER TO REPAIR THE ROADWAY PAVEMENT AND PAVED SHOULDERS.

DEPTH OF REMOVAL SHALL TYPICALLY BE 3 IN. UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

THE INTENT OF THIS ITEM OF WORK IS TO REPAIR SEVERE OR DEEP POTHoles, LOW AREAS AND AREAS WITH LOOSE OR MISSING ASPHALT. AREAS WHICH HAVE EXTENSIVE CRACKING BUT ARE STRUCTURALLY SOUND SHALL NOT USE THIS ITEM.

THE FOLLOWING CONTINGENCY QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY

ITEM 251 - PARTIAL DEPTH PAVEMENT REPAIR 1500 SQ.YD.

FIELD OFFICE

THERE IS NO PAY QUANTITY PROVIDED FOR A FIELD OFFICE IN THESE PLANS.

CELLULAR PHONE

THE CONTRACTOR SHALL PROVIDE TWO (2) CELLULAR PHONES FOR USE BY ODOT ENGINEERS/SUPERVISORS/INSPECTORS.

PAYMENT FOR ALL MATERIAL, LABOR AND EQUIPMENT, INSTALLATION AND MAINTENANCE SHALL BE MADE AT THE CONTRACT BID PRICE FOR ITEM 690 - CELLULAR PHONE.

ITEM 446 - ASPHALT CONCRETE SURFACE COURSE, TYPE 1H, AS PER PLAN

THE GRADATION FOR THIS ITEM SHALL BE AS PER 441.02, TABLE A, TYPE 1, SURFACE MEDIUM. ALL OTHER SPECIFICATIONS SHALL BE AS TYPE 1H.

CALCULATED  
KAS  
CHECKED  
LDH

GENERAL NOTES

LAKE COUNTY  
LAK-306-0.00