

I:\PROJECTS\PID19489\19489CGA.DGN 19-OCT-1999 10:49AM jgrmovse

SHEET NUMBER										ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	CALCULATED	K.A.S.	CHECKED	LDH
4	5	9	12	13	14														
	410									203	60000	410	STA.	LINEAR GRADING					
	1500									251	01000	1500	SQ.YD.	PARTIAL DEPTH PAVEMENT REPAIR					
				69212						254	01001	69212	SQ.YD.	PAVEMENT PLANING, BITUMINOUS, AS PER PLAN					
				7018						407	10000	7018	GALLON	TACK COAT					5
				3511						407	14000	3511	GALLON	TACK COAT FOR INTERMEDIATE COURSE					5
				2852						446	50001	2852	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1H, AS PER PLAN					4
				974						448	46020	974	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG 64-22					
	12									604	09001	12	EACH	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN					
	3									604	20601	3	EACH	INLET ADJUSTED TO GRADE, AS PER PLAN					
	1									604	34501	1	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN					
	2									604	39501	2	EACH	MONUMENT ADJUSTED TO GRADE, AS PER PLAN					
	500									SPECIAL	60450000	500	POUND	MISCELLANEOUS METAL					
			387.5							606	13000	387.5	LIN.FT.	GUARDRAIL, TYPE 5					6
			1							606	22010	1	EACH	ANCHOR ASSEMBLY, TYPE E-98					7
			1							606	25000	1	EACH	ANCHOR ASSEMBLY, TYPE A					
			1							606	26500	1	EACH	ANCHOR ASSEMBLY, TYPE T					
		40								614	12460	40	EACH	WORK ZONE MARKING SIGN					
	75									614	13000	75	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC					
		4.13								614	21100	4.13	MILE	TEMPORARY CENTER LINE, CLASS I, 642 PAINT					
		4.13								614	21500	4.13	MILE	TEMPORARY CENTER LINE, CLASS II, 642 PAINT					
		132								614	26200	132	LIN.FT.	TEMPORARY STOP BAR, CLASS I, 642 PAINT					
		96								614	27200	96	LIN.FT.	TEMPORARY CROSSWALK, CLASS I, 642 PAINT					
		253								617	10100	253	CU.YD.	COMPACTED AGGREGATE, TYPE A					
	5									632	26500	5	EACH	DETECTOR LOOP					
				8.26						642	00102	8.26	MILE	EDGELINE, TYPE 2					
				4.13						642	00302	4.13	MILE	CENTERLINE, TYPE 2					
				198						642	00702	198	LIN.FT.	TRANSVERSE LINE, TYPE 2					
				200						642	00402	200	LIN.FT.	CHANNELIZING LINE, TYPE 2					
				114						642	00502	114	LIN.FT.	STOP LINE, TYPE 2					
				48						642	00602	48	LIN.FT.	CROSS WALK LINE, TYPE 2					
				2						642	01102	2	EACH	SCHOOL SYMBOL MARKING (72"), TYPE 2					
				4						642	01302	4	EACH	LANE ARROW, TYPE 2					
				2						642	01402	2	EACH	WORD ON PAVEMENT (72"), TYPE 2					
				4846						659	10000	4846	SQ.YD.	SEEDING AND MULCHING					6
				1						659	20000	1	TON	COMMERCIAL FERTILIZER					
	2									SPECIAL	69086000	2	EACH	CELLULAR PHONE					
										614	11000		LUMP	MAINTAINING TRAFFIC					
										623	10000		LUMP	CONSTRUCTION LAYOUT STAKES					
										624	10000		LUMP	MOBILIZATION					

GENERAL SUMMARY

LAK-306-0.00