621 - PAVEMENT MARKING

CALC: R.C. 9-79
CHK: PCB 10-79
Revised By DEH 8-27-80

FED. RD. DIVISION	STATE	PROJECT	
5	OHIO		

LAKE COUNTY
LAK-306-6.15

56/101

4/8

ROADWAY		STATION	TO STATION	4" LANE LINES L.F.	4" CENTER LINE SOLID DOUBLE L.F.	8" CHANNELIZING LINES L.F.	24" STOP LINES L.F.	6" CROSSWALK LINES L.F.	12" BROAD TRANSVERSE LINES (WHITE) L.F.	8" BROAD TRANSVERSE LINES (YELLOW) L.F.		LANE ARROWS EA.	WORD "ONLY" ON PAVEMENT EA.			REMOVAL OF CENTERLINE L.F.	REMOVAL OF LANE LINE L.F.	REMOVAL OF STOP LINE L.F.
S.R. 306		8+58	9+46		88	88												
		9+48					28											
		9+82						58										
		9+58						68										
									•									
		10+27	11+18			137			172									
		10+40	10+49				39											
		10+49	15+90	1342	641	283												
		15+90	20+00	820	820					295								
		20+00	27+67	1530	767													
		27+67					27											
		27+95						58										
		27+81						56										
		28+82					26											
		10+98	11+16					56										
		10+34										3						
		11+40											3					
		12+10										3						
		16+41										3						
		26+35	28+38															
U.S. 20		78+56	79+43		92	92												
		79+48					27											
		79+63	79+86					48										
		79+89	79+62					50										
		80+67	80+79					65										
		80+93	80+80					47										
		80+79	80+84				31											
		80+79	83+68		287	391											289	289	30
		80+86	81+46						60									
		81+28	81+48				28											
		81+13										2						
		81+53											2					
		81+73										1						
		82+13											1					
		83+13										3						
TYLER BLVD.		100+41	101+00			160			191									
		100+52					12											
		100+52	101+60		108	60												
		100+77	100+95				22											
		101+20	101+60									2	2					
		TOTALS		3496	2495	1411	240	490	403	295		17	8				289	289	30
			MILES	0.70	0.51	0.27													

		STATION	TO STATION

NOTE: * DELINEATORS ARE TO BE PLACED ON THE RIGHT SIDE OF THE MAINLINE PAVEMENT FACING THE DIRECTION OF TRAVEL. ON RAMPS THEY ARE TO BE PLACED ON THE RIGHT AND/OR LEFT, AS TABULATED, FACING THE DIRECTION OF TRAVEL. SEE DELINEATOR DETAILS.

620 - DELINEATORS

PARTICIPATION	RAMP ROADWAY	STATION	TO STATION	SIDE *	INTERVAL	TYPE A POST	TYPE A BRACKET	TYPE D POST	TYPE D BRACKET