

MAINTENANCE OF TRAFFIC SUB-SUMMARY

WORK ZONE PAVEMENT MARKINGS SUB-SUMMARY				614 TEMPORARY 4" EDGE LINE WHITE CLASS I 947.03 TYPE C	614 TEMPORARY 4" DOUBLE YELLOW CENTERLINE CLASS I 947.03 TYPE C	614 TEMPORARY STOP LINES CLASS I 947.03 TYPE C	614 TEMPORARY 4" EDGE LINE WHITE CLASS I 621 PAINT	614 TEMPORARY 4" DOUBLE YELLOW CENTERLINE CLASS I 621 PAINT	614 TEMPORARY STOP LINE CLASS I 621 PAINT
SECTION	PHASE	SIDE	STA. TO STA.	MILES	MILES	LIN. FT.	MILES	MILES	LIN. FT.
1	A	LT.	STA. 25+00 TO STA. 64+70.74				7,942	3,971	
1	A	LT.	STA. 35+10						11
1	A	LT.	STA. 35+85						11
1	A	LT.	STA. 35+93						11
1	A	LT.	STA. 36+68						11
SUBTOTAL SECTION 1 PHASE A				-	-		7,942 L.F.	3,971 L.F.	44 L.F.
1	B	RT.	STA. 25+00 TO STA. 62+50	3,750	3,750				
1	B	RT.	STA. 62+50 TO STA. 64+57				414	207	
1	B	RT.	STA. 35+35			11			
1	B	RT.	STA. 36+04			11			
1	B	RT.	STA. 36+18			11			
1	B	RT.	STA. 36+85			11			
1	B	LT.	STA. 9+25 (ADKINS RD.)			11			11
SUBTOTAL SECTION 1 PHASE B				3,750 L.F.	3,750 L.F.	55 L.F.	414 L.F.	207 L.F.	11 L.F.
2	A	RT.	STA. 62+50 TO STA. 93+00				6,100	3,050	
2	A	RT.	STA. 64+50						11
2	A	RT.	STA. 65+14						11
SUBTOTAL SECTION 2 PHASE A				-	-		6,100 L.F.	3,050 L.F.	22 L.F.
2	B	LT.	STA. 62+50 TO STA. 89+00	2,650	2,650				
2	B	LT.	STA. 89+00 TO STA. 101+75				2,550	1,275	
2	B	RT.	STA. 10+75 (OHIO STREET)			11			11
2	B	RT.	STA. 11+75 (BELLFLOWER RD.)			11			11
2	B	LT.	STA. 64+17			11			
2	B	LT.	STA. 65+15			11			
2	B	LT.	STA. 97+54						11
2	B	LT.	STA. 98+54						11
SUBTOTAL SECTION 2 PHASE B				2,650 L.F.	2,650 L.F.	44 L.F.	2,550 L.F.	1,275 L.F.	44 L.F.
2	C	RT.	STA. 62+50 TO STA. 99+00	3,650	3,650				
2	C	RT.	STA. 99+00 TO STA. 101+75				550	275	
2	C	RT.	STA. 64+50			11			
2	C	RT.	STA. 65+30			11			
2	C	RT.	STA. 97+82			11			
2	C	RT.	STA. 98+70			11			
SUBTOTAL SECTION 2 PHASE C				3,650 L.F.	3,650 L.F.	44 L.F.	550 L.F.	275 L.F.	-
3	A	RT.	STA. 124+93 TO STA. 139+55				2,924	1,462	
SUBTOTAL SECTION 3 PHASE A							2,924 L.F.	1,462 L.F.	-
3	B	LT.	STA. 124+77 TO STA. 127+45				536	268	
3	B	LT.	STA. 127+45 TO STA. 136+25	880	880				
3	B	LT.	STA. 136+25 TO STA. 149+78				2,706	1,353	
3	B	LT.	STA. 149+32						11
3	B	LT.	STA. 150+40						11
3	B	LT.	STA. 7+00 TO STA. 14+00(LAKESHORE BLVD.)				1,400	700	
3	B	LT.	STA. 9+00 (LAKESHORE BLVD.)						11
3	B	LT.	STA. 10+55 (LAKESHORE BLVD.)						11
SUBTOTAL SECTION 3 PHASE B				880 L.F.	880 L.F.	-	4,642 L.F.	2,321 L.F.	44 L.F.
3	C	RT.	STA. 124+77 TO STA. 127+45				536	268	
3	C	RT.	STA. 127+45 TO STA. 149+50	2,205	2,205				
3	C	RT.	STA. 6+25 TO STA. 15+35(LAKESHORE BLVD.)				1,820	910	
3	C	RT.	STA. 149+30			11			
3	C	RT.	STA. 9+30 (LAKESHORE BLVD.)						11
3	C	RT.	STA. 9+48 (LAKESHORE BLVD.)						11
3	C	LT.	STA. 9+25 (CLEAR MONT DR.)			11			11
SUBTOTAL SECTION 3 PHASE C				2,205 L.F.	2,205 L.F.	22 L.F.	2,356 L.F.	1,178 L.F.	33 L.F.
3	D	RT.	STA. 150+60			11			
3	D	LT.	STA. 6+25 TO STA. 15+35(LAKESHORE BLVD.)	910	910				
3	D	LT.	STA. 9+68 (LAKESHORE BLVD.)			11			
3	D	LT.	STA. 9+75 (LAKESHORE BLVD.)			11			
SUBTOTAL SECTION 3 PHASE D				910 L.F.	910 L.F.	33 L.F.	-	-	-

WORK ZONE PAVEMENT MARKINGS SUB-SUMMARY				614 TEMPORARY 4" EDGE LINE WHITE CLASS I 947.03 TYPE C	614 TEMPORARY 4" DOUBLE YELLOW CENTERLINE CLASS I 947.03 TYPE C	614 TEMPORARY STOP LINES CLASS I 947.03 TYPE C	614 TEMPORARY 4" EDGE LINE WHITE CLASS I 621 PAINT	614 TEMPORARY 4" DOUBLE YELLOW CENTERLINE CLASS I 621 PAINT	614 TEMPORARY STOP LINE CLASS I 621 PAINT	
SECTION	PHASE	SIDE	STA. TO STA.	MILES	MILES	LIN. FT.	MILES	MILES	LIN. FT.	
4	A	LT.	STA. 99+00 TO STA. 127+45							
4	A	RT.	STA. 10+75 (JEREMY DR.)			11		5,690	2,845	
SUBTOTAL SECTION 4 PHASE A				-	-	11 L.F.		5,690 L.F.	2,845 L.F.	11 L.F.
4	B	RT.	STA. 99+00 TO STA. 127+45	2,845	2,845					
4	B	RT.	STA. 9+25 (BUTTERNUT LANE)			11			11	
SUBTOTAL SECTION 4 PHASE B				2,845 L.F.	2,845 L.F.	11 L.F.	-	-	11 L.F.	
GRAND TOTAL TEMPORARY PAVEMENT MARKINGS				16,890 L.F.	16,890 L.F.	220 L.F.	33,168 L.F.	16,584 L.F.	220 L.F.	
GRAND TOTAL TEMPORARY PAVEMENT MARKINGS				3.20 MILES	3.20 MILES	220 L.F.	6.28 MILES	3.14 MILES	220 L.F.	