

FOR TYPICAL SECTIONS SEE SHEETS 4 THRU 13
 * INCLUDES EXTRA AREA BY COMPUTER CALCULATION
 ** WIDENING AREA ONLY

PAVEMENT SUB-SUMMARY

PAVEMENT SUB-SUMMARY							202	202	203	254	301	304	310	403	404	407	451
STREET NAME	STATION TO STATION	LENGTH FEET	AVERAGE WIDTH FEET		PAVEMENT AREA SQ. YDS.		PAVEMENT REMOVED SQ. YDS.	CURB AND GUTTER REMOVED LIN. FT.	SUBGRADE COMPACTION SQ. YDS.	PAVEMENT PLANNING, BITUMINOUS (1 1/4" THICKNESS) SQ. YDS.	6" BITUMINOUS AGGREGATE BASE, AC-20 CU. YDS.	4" AGGREGATE BASE AS PER PLAN CU. YDS.	6" SUBBASE TYPE II AS PER PLAN CU. YDS.	0" MINIMUM (1/2" AVERAGE) ASPHALT CONCRETE AC-20 CU. YDS.	1 1/4" ASPHALT CONCRETE AC-20 CU. YDS.	TACK COAT @ .075 GAL/SQ 10 GAL.	10" REINFORCED CONCRETE PAVEMENT, AS PER PLAN SQ. YD.
			**	**	**	**											
S.R. 306	STA. 25+00.00 TO STA. 26+08.04	108.04	63.5	22.8	762.3	273.1				513.2	45.5	30.3	45.5	10.6	26.5	57.2	
S.R. 306	STA. 26+08.04 TO STA. 30+06.04	398.60	64.0		2,834.5			2878.8					479.8				2878.8
S.R. 306	STA. 30+06.64 TO STA. 37+76.82	770.18	64.0		4,963.4			5562.4					927.1				5562.4
S.R. 306	STA. 37+76.82 TO STA. 38+56.82	80.00	58.0		515.6			524.4					87.4				524.4
S.R. 306	STA. 38+56.82 TO STA. 63+30.06	2473.24	52.0		14,564.6			14,564.6					2,427.4				14,564.6
S.R. 306	STA. 63+30.06 TO STA. 64+10.06	80.00	58.0		515.6			524.4					87.4				524.4
S.R. 306	STA. 64+10.06 TO STA. 68+76.90	466.84	64.0		3,319.8			3,371.6					561.9				3,371.6
S.R. 306	STA. 68+76.90 TO STA. 69+56.90	80.00	58.0		515.6			524.4					87.4				524.4
S.R. 306	STA. 69+56.90 TO STA. 149+62.89	8006.00	52.0		46,256.9			47,164.4					7,860.7				47,164.4
S.R. 306	STA. 150+03.71 TO STA. 151+75.00	171.29	40.0		761.3			780.3					130.1				780.3
S.R. 306	STA. 151+75.00 TO STA. 153+90.00	215.00	30.5	11.3	728.6	268.8			507.6	44.8	29.9	44.8	10.1	25.3	54.7		
ADKINS RD.	STA. 8+64.81 TO STA. 9+17.31	52.50	23.3	3.8	135.6	21.9			125.4	3.7	2.4	3.7	1.88	4.7	10.2		
ADKINS RD.	STA. 9+17.31 TO STA. 9+64.18	78.87	25.0		277.7 *			277.7					46.3				277.7
BROWNELL RD.	STA. 8+48.00 TO STA. 9+31.60	83.60	25.0		232.2		241.5	241.5					40.3				241.5
BROWNELL RD.	STA. 9+31.60 TO STA. 9+68.00	36.4	25.0		167.4 *		56.1	167.4					27.9				167.4
ERIE DR.	STA. 7+98.00 TO STA. 8+88.00	90.0	17.7	5.2	176.5	51.8			176.5	8.6	5.8	8.6	2.9	7.2	13.2		
ERIE DR.	STA. 8+88.00 TO STA. 9+16.33	28.33	24.0		75.6			78.7					13.1				78.7
ERIE DR.	STA. 9+16.33 TO STA. 9+68.00	51.67	24.0		489.5 *			489.5					81.6				489.5
ENFIELD DR.	STA. 8+65.00 TO STA. 9+33.98	68.98	25.0		191.6		199.3	199.3					31.9				199.3
ENFIELD DR.	STA. 9+33.98 TO STA. 9+74.00	40.02	25.0		178.8 *		52.1	178.8					29.8				178.8
CULVER BLVD.	STA. 8+04.00 TO STA. 8+34.00	30.00	20.5	3.5	68.3	11.7			63.3	2.0	1.3	2.0	1.0	2.4	5.1		
CULVER BLVD.	STA. 8+34.00 TO STA. 9+37.63	103.63	22.0		253.3			264.8					44.1				264.8
CULVER BLVD.	STA. 9+37.63 TO STA. 9+74.00	36.37	22.0		155.2 *			155.2					25.9				155.2
WELLAND DR.	STA. 8+05.00 TO STA. 8+50.00	45.00	22.0	4.0	110.0	20.0			100.0	3.3	2.2	3.3	1.5	3.8	8.3		
WELLAND DR.	STA. 8+50.00 TO STA. 9+34.03	84.03	24.0		224.1			233.4					38.9				233.4
WELLAND DR.	STA. 9+34.03 TO STA. 9+74.00	39.97	24.0		174.1 *			174.2					29.0				174.2
ANDOVER DR.	STA. 8+84.00 TO STA. 9+37.60	53.60	25.0		148.9		154.8	154.8					25.8				154.8
ANDOVER DR.	STA. 9+37.60 TO STA. 9+74.00	36.40	25.0		167.4 *		53.7	167.4					27.9				167.4
FARNHAM DR.	STA. 7+59.00 TO STA. 8+34.00	75.00	22.0	4.3	183.3	35.4			164.6	5.9	3.9	5.9	2.5	6.4	18.3		
FARNHAM DR.	STA. 8+34.00 TO STA. 9+37.61	103.61	24.0		276.3			287.8					48.0				287.8
FARNHAM DR.	STA. 9+37.61 TO STA. 9+74.00	36.39	24.0		163.4 *			163.4									
OHIO ST.	STA. 10+32.00 TO STA. 10+83.19	51.19	35.0		335.6 *								55.9				335.6
TOTALS							758	70	79,465	1,651	114	76	13,330	31	76	167	79,302