

FOR TYPICAL SECTIONS SEE SHEETS 4 THRU 13
 * INCLUDES EXTRA AREA BY COMPUTER CALCULATION
 ** WIDENING AREA ONLY

PAVEMENT SUB-SUMMARY

PAVEMENT SUB-SUMMARY						202	202	203	254	301	304	310	403	404	407	451
STREET NAME	STATION TO STATION	LENGTH FEET	AVERAGE WIDTH FEET		PAVEMENT AREA SQ. YDS.	PAVEMENT REMOVED SQ. YDS.	CURB AND GUTTER REMOVED LIN. FT.	SUBGRADE COMPACTION SQ. YDS.	PAVEMENT PLANNING, BITUMINOUS (1 1/4" THICKNESS) SQ. YDS.	6" BITUMINOUS AGGREGATE BASE, AC-20 CU. YDS.	4" AGGREGATE BASE AS PER PLAN CU. YDS.	6" SUBBASE TYPE II AS PER PLAN CU. YDS.	0" MINIMUM (1/2" AVERAGE) ASPHALT CONCRETE AC-20 CU. YDS.	1 1/4" ASPHALT CONCRETE AC-20 CU. YDS.	TACK COAT @ .075 GAL/SQ YD GAL.	10" REINFORCED CONCRETE PAVEMENT, AS PER PLAN SQ. YD.
			**	**												
OHIO ST.	STA. 10+83.19 TO STA. 11+32.00	48.81	35.0		189.8		97.6	195.2				32.5				195.2
HODGSON RD.	STA. 8+33.00 TO STA. 9+16.31	83.31	25.0		231.4	240.7		240.7				40.1				240.7
HODGSON RD.	STA. 9+16.31 TO STA. 9+68.00	51.69	25.0		273.8 *	299.1		273.8				45.6				273.8
HAWK AVE.	STA. 10+26.00 TO STA. 10+62.89	36.89	24.0		163.4 *			163.4				27.2				163.4
HAWK AVE.	STA. 10+62.89 TO STA. 11+46.00	83.11	24.0		221.6			230.9				38.5				230.9
HAWK AVE.	STA. 11+46.00 TO STA. 11+91.00	45.00	22.3	3.8	111.3	18.8			136.7	3.1	2.1	3.1	1.6	3.9	8.3	
TEXAS AVE.	STA. 10+26.00 TO STA. 10+62.89	36.89	24.0		164.7 *			164.7				27.5				164.7
TEXAS AVE.	STA. 10+62.89 TO STA. 11+26.00	63.11	24.0		168.3			175.3				29.2				175.3
TEXAS AVE.	STA. 11+26.00 TO STA. 11+86.00	60.00	22.3	3.8	148.3	25.0			136.7	4.2	2.8	4.2	2.1	5.2	11.1	
WEST BELLFLOWER RD.	STA. 8+69.00 TO STA. 9+23.50	54.50	33.0		199.8	205.9		205.9				41.8				205.9
WEST BELLFLOWER RD.	STA. 9+23.50 TO STA. 9+74.00	50.50	33.0		373.1 *	447.8		373.1				62.2				373.1
EAST BELLFLOWER RD.	STA. 11+26.00 TO STA. 11+78.64	52.64	36.0		358.4 *	348.1		358.4				59.7				358.4
EAST BELLFLOWER RD.	STA. 11+78.64 TO STA. 12+31.00	52.36	36.0		209.4	215.3		215.3				35.9				215.3
OLD FARM LN.	STA. 8+89.00 TO STA. 9+37.50	48.50	33.0		177.8	183.2		183.2				30.5				183.2
OLD FARM LN.	STA. 9+37.50 TO STA. 9+74.00	36.50	33.0		200.1 *	232.2		200.1				33.4				200.1
BUTTERNUT LN.	STA. 8+74.00 TO STA. 9+04.00	30.00	21.5	2.5	71.7	8.3			70.0	1.4	.9	1.4	1.0	2.5	7.2	
BUTTERNUT LN.	STA. 9+04.00 TO STA. 9+36.85	32.85	22.0		80.3			84.0				14.0				84.0
BUTTERNUT LN.	STA. 9+36.85 TO STA. 9+74.00	37.15	22.0		152.8 *			152.8				25.5				152.8
JEREMY AVE.	STA. 10+26.00 TO STA. 10+62.10	36.10	22.0		154.6 *			154.6				25.8				154.6
JEREMY AVE.	STA. 10+62.10 TO STA. 11+26.00	63.90	22.0		156.2			163.3				27.2				163.3
JEREMY AVE.	STA. 11+26.00 TO STA. 11+56.00	30.00	20.5	3.5	68.3	11.7			63.3	2.0	1.3	2.0	1.0	2.4	5.1	
PORT ROYAL CT.	STA. 9+04.00 TO STA. 9+38.50	34.50	24.0		92.0	95.8		95.8				16.0				95.8
PORT ROYAL CT.	STA. 9+38.50 TO STA. 9+74.00	35.48	24.0		160.1 *	244.9		160.1				26.7				160.1
FAYE LN.	STA. 10+26.00 TO STA. 10+62.52	36.52	24.0		160.7 *	373.1		160.7				26.8				160.7
FAYE LN.	STA. 10+62.52 TO STA. 11+36.00	73.48	24.0		196.0	204.1		204.1				34.0				204.1
SHENANDOAH DR.	STA. 8+79.00 TO STA. 9+38.50	59.50	24.0		158.7	165.3		165.3				27.5				165.3
SHENANDOAH DR.	STA. 9+38.50 TO STA. 9+74.00	35.50	24.0		161.0 *	242.2		161.0				26.8				161.0
FORD DR.	STA. 10+26.00 TO STA. 10+61.54	35.54	24.0		161.0 *	171.4		161.0				26.8				161.0
FORD DR.	STA. 10+61.54 TO STA. 11+36.00	74.46	24.0		198.6	206.8		206.8				34.5				206.8
COLE DR.	STA. 10+26.00 TO STA. 10+61.50	35.50	24.0		161.0 *			98.6				16.4				98.6
COLE DR.	STA. 10+61.50 TO STA. 11+61.00	99.50	24.0		265.3			276.4				46.1				276.4
COLE DR.	STA. 11+61.00 TO STA 12+73.50	112.50	21.0	4.3	262.5	35.4			218.8	11.5	7.6	11.5	3.6	9.1	19.7	
TOTALS						3,876	98	5225	625	22	15	901	9	23	51	5225

LAK - 306 - 7.12