FOR ADDITIONAL SANITARY SEWER DETAILS SEE SHEETS 329 THROUGH 331.

SANITARY SEWER CONNECTION SCHEDULE

SANITARY SEWER CONNECTION SCHEDULE						603	603	603											
						6" CONDUIT, TYPE B, AS PER PLAN, 706.08 W/JOINTS AS PER 706.12	6" CONDUIT, TYPE C, AS PER PLAN, 706.08 W/JOINTS AS PER 706.12	6" CONDUIT, TYPE B, AS PER PLAN, DUCTILE IRON PIPE ANSI CL52 W/JOINTS AND FITTINGS		COUPLING VITRIFIED CLAY TO VITRIFIED CLAY	COUPLING VITRIFIED CLAY TO DUCTILE IRON		45° BEND	PLUG EXISTING CONNECTION	PLUG FUTURE CONNECTION		ENCASE RISER CONNECTION	8" x 6" WYE CONNECTION	
STREET NAME	SHEET NO.	REF. NUMBER	CENTERLINE STATION	SIDE	HOUSE NUMBER	LIN. FT.	LIN. FT.	LIN. FT.		EACH	EACH		EACH	EACH	EACH		EACH	EACH	
S.R. 306	88	SC–1	25+51.00	LT.	----	18				1					1				
S.R. 306	89	SC–1	27+69.00	RT.	7495	25		10		1	2		2						
S.R. 306	89	SC–2	28+97.00	RT.	7483	25		10		1	2		2						
S.R. 306	89	SC–3	28+78.00	LT.	----	25				1					1				
S.R. 306	90	SC–1	29+95.00	RT.	7473	25		10		1	2		2						
S.R. 306	90	SC–2	31+27.00	RT.	----	25		10		1	2		2						
S.R. 306	90	SC–3	32+96.00	RT.	7441	25		10		1	2		2						
S.R. 306	90	SC–4	33+41.00	LT.	7337	20				1					1				
S.R. 306	91	SC–1	34+94.00	RT.	7419	27		10		1	2		2						
S.R. 306	91	SC–2	36+12.00	RT.	7413	28		10		1	2		2						
S.R. 306	91	SC–3	37+73.00	RT.	----	29		10		1	2		2						
S.R. 306	91	SC–4	34+90.00	LT.	7336	20				1					1				
S.R. 306	92	SC–1	39+04.00	RT.	7387	22		10		1	2		2						
S.R. 306	92	SC–2	39+95.00	RT.	7371	22		10		1	2		2						
S.R. 306	92	SC–3	41+43.00	RT.	7357	22		10		1	2		2						
S.R. 306	93	SC–1	42+75.00	RT.	7347	24		10		1	2		2	1					
S.R. 306	93	SC–2	43+80.00	RT.	7325	24		10		1	2		2	1					
S.R. 306	93	SC–3	42+30.00	LT.	----	15				1									
S.R. 306	94	SC–1	46+56.00	RT.	7317	20		10		1	2		2						
S.R. 306	94	SC–2	47+72.00	RT.	7305	20		10		1	2		2						
S.R. 306	94	SC–3	49+15.00	RT.	7285	20		10		1	2		2						
S.R. 306	94	SC–4	49+65.00	RT.	7281	20		10		1	2		2						
S.R. 306	95	SC–1	51+10.00	RT.	----	20		10		1	2		2						
S.R. 306	95	SC–2	51+54.00	RT.	7255	20		10		1	2		2						
S.R. 306	95	SC–4	53+92.00	RT.	7239	20		10		1	2		2						
S.R. 306	95	SC–5	53+86.00	LT.	----	15				1					1				
S.R. 306	96	SC–1	54+98.00	RT.	7229	20		10		1	2		2						
S.R. 306	96	SC–2	55+99.00	RT.	7217	20		10		1	2		2						
S.R. 306	96	SC–3	55+40.00	LT.	7230	18				1					1				
S.R. 306	97	SC–1	58+43.00	RT.	----	20		10		1	2		2						
S.R. 306	97	SC–2	59+64.00	RT.	7193	20		10		1	2		2						
S.R. 306	97	SC–3	61+30.00	RT.	7181	20		10		1	2		2						
S.R. 306	99	SC–1	68+81.00	LT.	7333	35		10		1	2		2						
S.R. 306	100	SC–1	71+18.00	RT.	7079	20		10		1	2		2						
S.R. 306	100	SC–2	69+83.00	LT.	----									1					
S.R. 306	100	SC–3	70+43.00	LT.	----		6							1	1			1	
S.R. 306	100	SC–4	71+25.00	LT.	----		6							1	1			1	
S.R. 306	100	SC–5	71+91.00	LT.	----		6							1	1			1	
S.R. 306	100	SC–6	72+60.00	LT.	----		6							1	1			1	
S.R. 306	100	SC–1	73+40.00	LT.	----		6							1	1			1	
S.R. 306	101	SC–2	74+20.00	LT.	----		6							1	1			1	
S.R. 306	101	SC–3	74+73.00	LT.	----		6							1	1			1	
S.R. 306	101	SC–4	75+61.00	LT.	----		6							1	1			1	
S.R. 306	101	SC–5	76+22.00	LT.	----		6							1	1			1	
S.R. 306	101	SC–6	76+95.00	LT.	----		6							1	1			1	
				TOTALS		749	60	270		34	54		54	13	16			10	

NOTE
COST FOR COUPLINGS, BENDS, PLUGS, ENCASEMENT & WYE CONNECTIONS ARE INCLUDED IN THE UNIT PRICE BID FOR VARIOUS ITEM 603 CONDUITS. THESE ITEMS ARE NOT CARRIED TO THE GENERAL SUMMARY.