

# TRAFFIC CONTROL GENERAL SUMMARY

CALC. BY S.J.G.  
 DATE 12/89  
 CHKD. BY M.C.C.  
 DATE 12/89

LAKE COUNTY  
 LAK - 306 - 7.12

OHIO  
 FHWA REGION 5  
 336  
 452

ITEM	ITEM EXT.	SHEET NUMBER																				ITEM	ITEM EXT.	QUANT.	UNIT	DESCRIPTION	
		367	366	362	361	360	359	358	357	356	355	354	351	350	349	348	346	344	341	338	335						
621	10008											.07	4.51									621	10008	4.58	MILE	LANE LINE	
621	20100											.36	2.63									621	20100	2.99	MILE	CENTER LINE	
621	30100											375	977									621	30100	1352	LIN. FT	CHANNELIZING LINE	
621	40100											275	612									621	40100	887	LIN. FT	STOP LINE	
621	50100											440	1383									621	50100	1823	LIN. FT	CROSSWALK LINE	
621	60100											172	262									621	60100	434	LIN. FT	TRANSVERSE LINE	
621	70000												30									621	70000	30	SQ.FT	ISLAND MARKING	
621	76500											3	14									621	76500	17	EACH	LANE ARROW	
621	80000											3	3									621	80000	6	EACH	WORD ON PAVEMENT, 72"	
621	90300											1	1									621	90300	2	EACH	SCHOOL SYMBOL MARKING, 72"	
625	25102																					625	25102	29	LIN. FT	CONDUIT, 1", 713.07, TYPE DB	
625	25402	4000	1583												810	240	133	40	220	194		625	25402	7220	LIN. FT	CONDUIT, 2", 713.07, TYPE DB	
625	25502																					625	25502	389	LIN. FT	CONDUIT, 3", 713.07, TYPE DB	
625	25802																					625	25802	1197	LIN. FT	CONDUIT, CONCRETE ENCASED, 3", 713.07	
625	29000	4000	1748												810	240	409	347	805	447		625	29000	8806	LIN. FT	TRENCH	
625	30700	22	10												7	4	4	3	6	4		625	30700	60	EACH	PULL BOX, 713.08, 18"	
625	30706																					625	30706	13	EACH	PULL BOX, 713.08, 24"	
625	32000																					625	32000	32	EACH	GROUND ROD	
630	00000												2.96									630	00000	9.2	CU. YD.	CONCRETE FOR ANCHOR BASE FOUNDATIONS	
630	02100												52	286	338	377	338	234				630	02100	1625	LIN. FT.	GROUND MOUNTED SUPPORTS, NO. 2 POST	
630	03100												182	208	156	143	156	208				630	03100	1053	LIN. FT.	GROUND MOUNTED SUPPORTS, NO. 3 POST	
630	08500												23									630	08500	23	EACH	STREET NAME SIGN SUPPORT	
630	10100																					630	10100	2	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-16.20, DESIGN No.1, W/ 23' ARM	
630	10300																					630	10300	2	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-16.20, DESIGN No.3, W/ 35' ARM	
630	79501																					75	630	79501	75	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED, AS PER PLAN
630	80100												78.3	89.5	82.3	91.8	84.0	93.0				630	80100	519	SQ. FT.	SIGN, FLAT SHEET	
630	80102													37.8	18.9	12.6	25.2	58.9				630	80102	153	SQ. FT.	SIGN, FLAT SHEET, TYPE G	
630	80500													23								630	80500	23	EACH	SIGN, DOUBLE FACED, STREET NAME	
630	85000																					630	85000	98	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	
630	86006																					630	86006	78	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND STORAGE	
630	87100																					630	87100	1	EACH	REMOVAL OF OVERHEAD MOUNTED SIGN AND REERECTION	
630	89100																					630	89100	1	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND REERECTION, TYPE TC-12.30	
631	93000																					631	93000	2	EACH	SCHOOL SPEED LIMIT SIGN ASSEMBLY, 24"X42"	
631	93300																					631	93300	1	EACH	TIMER WITH ENCLOSURE	