

GENERAL

PROJECT DESCRIPTION

THIS PROJECT SHALL CONSIST OF THE SAFETY UPGRADING AND RESURFACING OF SR 44 FROM THE COUNTY LINE TO 0.29 MILES NORTH OF SR 84. ITEMS INCLUDED SHALL BE WEARING COURSE REMOVED, FULL DEPTH PAVEMENT REPAIR, ASPHALT CONCRETE OVERLAY, GUARDRAIL, DRAINAGE AND SIGNING.

RIGHT OF WAY

ALL WORK SHALL BE PERFORMED WITHIN THE EXISTING RIGHT OF WAY OR EASEMENTS.

EXISTING TYPICAL SECTIONS

EXISTING TYPICAL SECTIONS HAVE BEEN TAKEN FROM THE RECORDS AND ARE BELIEVED TO REPRESENT THE EXISTING PAVEMENT, BUT THE STATE OF OHIO DOES NOT GUARANTEE THE ACCURACY OF THE SAME.

FOR FURTHER INFORMATION IN REGARD TO THE EXISTING TYPICAL SECTIONS, THE CONTRACTOR SHALL REFER TO THE PREVIOUS CONSTRUCTION PLANS.

THESE PLANS MAY BE REVIEWED AT THE

OHIO DEPARTMENT TRANSPORTATION
DISTRICT 12 OFFICE
5500 TRANSPORTATION BOULEVARD
GARFIELD HEIGHTS, OHIO 44125

CONVERSION OF METRIC STANDARD DRAWINGS

THE METRIC STANDARD DRAWINGS REFERENCED IN THIS PLAN SHALL BE CONVERTED TO ENGLISH UNITS USING THE SI (METRIC) TO ENGLISH CONVERSION FACTORS PROVIDED IN SECTION 109.011 OF THE 1997 CONSTRUCTION AND MATERIALS SPECIFICATIONS. THE APPENDIX QF ASTM E 380 SHALL BE UTILIZED FOR ANY ADDITIONAL CONVERSION FACTORS REQUIRED. CONVERSIONS SHALL BE APPROPRIATELY PRECISE AND SHALL REFLECT STANDARD INDUSTRY ENGLISH VALUES WHERE SUITABLE.

CONTINGENCY QUANTITIES

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK FOR ITEMS DESIGNATED BY PLAN NOTE TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER. THE ACTUAL WORK LOCATIONS AND QUANTITIES USED FOR SUCH ITEMS SHALL BE INCORPORATED INTO THE FINAL CHANGE ORDER GOVERNING COMPLETION OF THIS PROJECT.

COOPERATION BETWEEN CONTRACTORS

THE CONTRACTOR SHALL COOPERATE AND COORDINATE HIS/HER OPERATIONS WITH THE CONTRACTORS ON OTHER PROJECTS THAT MAY BE IN FORCE DURING THE LIFE OF THE CONTRACT. NO WAIVER OF ANY PROVISIONS OF 105.07 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS IS INTENDED.

UTILITY OWNERSHIP

THE FOLLOWING UTILITIES AND OWNERS ARE LOCATED WITHIN THE WORK LIMITS OF THIS PROJECT. THE OHIO DEPARTMENT OF TRANSPORTATION HAS USED THE BEST AVAILABLE INFORMATION TO DETERMINE THE UTILITY COMPANIES SERVING THIS AREA, BUT CANNOT GUARANTEE THE UTILITY COMPANY LIST IS COMPLETE.

AMERITECH
13630 LORAIN AVE. 4th FLOOR
CLEVELAND, OHIO 44111
ATTN: SHELLY ARMSTRONG
VOICE: (216) 476-6142
FAX: (216) 476-6142

CITY OF PAINESVILLE
P.O. BOX 601
PAINESVILLE, OHIO 44077
ELECTRIC - THOMAS GREEN
(440) 352-9301 FAX: 357-1966
WATER - WILLIAM VARGYARS
(440) 352-9301 FAX: 639-4998

CLEVELAND ELECTRIC ILLUMINATING COMPANY
7755 AUBURN ROAD
PAINESVILLE, OHIO 44077
ATTN: RICH KERNEY, PHILLIP MULLET
VOICE: (440) 953-7751 OR (440)953-7741
FAX: (440) 953-7750

CONSUMERS OHIO WATER
LAKE ERIE DIVISION
P.O. BOX 960
8644 STATION STREET
MENTOR, OHIO 44061-0960
VOICE: (440) 255-3421
FAX: (440) 255-6522

EAST OHIO GAS
1201 EAST 55th STREET
CLEVELAND, OHIO 44103
ATTN: PAUL ARENDASH
VOICE: (216) 736-6675
FAX: (216) 736-6780

LAKE CO. DEPT. OF UTILITIES
ADMINISTRATION BUILDING
105 MAIN STREET
PAINESVILLE, OHIO 44077
ATTN: ALBERT SAARI
VOICE: (440) 946-2649
FAX: (440) 350-2666

MEDIA ONE
7820 DIVISION DRIVE
MENTOR, OHIO 44060
ATTN: DAVE MENCKE
VOICE: (440) 365-2556 EXT. 624

TCI CABLEVISION OF OHIO, INC.
SUITE #8
7757 AUBURN RD.
PAINESVILLE, OHIO 44077
ATTN: CATRINA
VOICE: (440)354-8000

JOINT SEALER

ALL REFERENCES TO 705.01 OR 705.02, APPEARING ON STANDARD DRAWINGS OR ON THE PLANS SHALL BE CONSIDERED TO READ 705.04.

CONSTRUCTION NOISE

ACTIVITIES AND LAND USE ADJACENT TO THIS PROJECT MAY BE AFFECTED BY CONSTRUCTION NOISE. IN ORDER TO MINIMIZE ANY ADVERSE CONSTRUCTION NOISE IMPACTS; JACK HAMMERS, HOE RAMS, AND PAVEMENT BREAKERS SHALL NOT BE OPERATED BETWEEN THE HOURS OF 9:00 PM AND 5:00 AM. IN ADDITION, ANY SUCH DEVICE SHALL NOT BE OPERATED AT ANY TIME IN SUCH A MANNER THAT THE NOISE CREATED SUBSTANTIALLY EXCEEDS THE NOISE CUSTOMARILY AND NECESSARILY ATTENDANT TO THE REASONABLE AND EFFICIENT PERFORMANCE OF SUCH EQUIPMENT.

EQUIPMENT AND MATERIAL STORAGE

IN ORDER TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC THE CONTRACTOR'S ATTENTION IS DIRECTED TO 614.03. IN ADDITION THE FOLLOWING PROVISIONS SHALL APPLY:

- 1) ANY REMOVED ITEMS SHALL NOT BE STORED ON THE RIGHT OF WAY FOR MORE THAN THIRTY DAYS.
- 2) THE STORAGE OF EQUIPMENT, MATERIALS, AND VEHICLES WITHIN THE HIGHWAY RIGHT OF WAY WILL BE PERMITTED. THE NUMBER OF AREAS AND EXACT LOCATIONS SHALL BE APPROVED BY THE ENGINEER.
- 3) ALL DISTURBED AREAS SHALL BE RETURNED TO THEIR ORIGINAL CONDITION AT NO EXPENSE TO THE STATE.

ROUNDING

THE ROUNDING AT SLOPE BREAKPOINTS SHOWN ON THE TYPICAL SECTIONS APPLY TO ALL CROSS-SECTIONS EVEN THOUGH OTHERWISE SHOWN.

ELEVATION DATUM

ALL ELEVATIONS ARE BASED ON U.S.G.S. DATUM.

WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. THE INSTALLATION AND OPERATION OF ALL TEMPORARY TRAFFIC CONTROL AND TEMPORARY TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS SHALL BE PROVIDED BY THE CONTRACTOR WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

ITEM 806 - FIELD OFFICE, TYPE B, AS PER PLAN

FOUR (4) OUTSIDE TELEPHONE LINES SHALL BE PROVIDED AND ASSIGNED AS LISTED BELOW:

- | | |
|------------|---|
| LINE 1 | FACSIMILE MACHINE & ONE PHONE |
| LINE 2 | COMPUTER MODEM |
| LINE 3 & 4 | RECORDED ANSWERING MACHINE & PHONES (3) |

IN ADDITION TO THE REQUIREMENTS STATED IN THE SPECIFICATIONS, THE FOLLOWING EQUIPMENT SHALL BE FOR USE AS DIRECTED BY THE ENGINEER:

ONE (1) CELLULAR PHONE.

ALL COSTS FOR THE FOUR (4) TELEPHONE LINES AND CELLULAR PHONE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 806 - FIELD OFFICE, TYPE B, AS PER PLAN.

GENERAL NOTES

LAK-44-0.01

PLOTTED BY: jgrmorse
PLOTTED FROM: 1:\PROJECTS\pid09866\09866.dgn
PLOT SUBMITTED: 10-FEB-1999 11:03
09866GNA.DGN

CALCULATED
KAS
CHECKED
ENF