

PAVEMENT WORK QUANTITIES FOR S.R. 44

DIRECTION	SIDE	LOCATION		LENGTH	PAVEMENT WORK AREA			SHOULDER WORK AREA			TOTAL AREA	202	203	203	304	305
					END WIDTHS		PAVEMENT AREA	END WIDTHS		SHOULDER AREA		PAVEMENT REMOVED	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	SUBGRADE COMPACTION	6" AGGREGATE BASE AS PER PLAN	9" CONCRETE BASE AS PER PLAN
					BEGIN	END		BEGIN	END							
		FROM	TO	LIN FT	FT	FT	SQ YD	FT	FT	SQ YD	SQ YD	CU YD	SQ YD	CU YD	SQ YD	
NORTHBOUND	OUT	44+00.00	52+57.49	857.5				10.0	10.0	953	953			1,000.4	166.7	952.8
	OUT	52+57.49	93+86.98	4,129.5				10.0	10.0	4,588	4,588			4,817.7	803.0	4,588.3
		SUB-TOTAL		4,987.0						5,541	5,541		***	5,818.1	969.7	5,541.1
	MED	88+28.43	88+78.43	50.0	0.0	12.0	33	5.0	5.0	28	61			63.9	10.6	61.1
	MED	88+78.43	91+73.45	295.0	12.0	12.0	393	5.0	5.0	164	557			573.7	95.6	557.3
	MED	91+73.45	93+86.98(BK)	213.5	12.0	29.8	496	5.0	5.0	119	614			626.2	104.4	614.4
	MED	108+00.00(AH)	108+98.45	98.5	29.8	38.0	371	5.0	5.0	55	425			430.9	71.8	425.4
	MED	108+98.45	109+48.50	50.0	38.0	38.0	211	5.0	5.0	28	239	10		241.9	40.3	239.1
	MED	109+48.50	109+82.50	34.0	50.0	50.0	189				189	21		188.9	31.5	188.9
	MED	109+82.50	109+99.50	17.0	37.3	37.3	70				70	12		70.4	11.7	70.4
	MED	109+99.50	110+10.00	10.5	25.0	25.0	29				29	9		29.2	4.9	29.2
		SUB-TOTAL		768.5			1,793			393	2,186	52	***	2,225.0	370.8	2,185.7
	MED	118+92.00	119+23.00	31.0			78			27	106			107.5	17.9	105.8
	MED	119+09.00	122+96.00	387.0				5.0	5.0	215	215			236.5	39.4	215.0
	OUT	120+05.48	122+16.00	210.5	5.0	12.0	199	10.0	10.0	234	433			444.4	74.1	432.7
	OUT	122+16.00	123+20.57	104.6				10.0	10.0	116	116			122.0	20.3	116.2
	MED	126+65.23	128+51.00	185.8				5.0	5.0	103	103	61		113.5	18.9	103.2
	MED	128+51.00	128+93.00	42.0			138			28	166	35		168.4	28.1	166.1
	OUT	129+53.00	132+05.23	252.2	6.2	0.0	87	10.0	10.0	280	367			381.1	63.5	367.1
		SUB-TOTAL		1,213.1			502			1,004	1,506	96	***	1,573.6	262.3	1,506.2
OUT	181+25.00	186+55.73	530.7				10.0	10.0	590	590		246	619.2	103.2	589.7	
MED	185+10.00	186+72.47	162.5				5.0	5.0	90	90		38	99.3	16.5	90.3	
OUT	187+72.15	193+00.00	527.8				10.0	10.0	586	586		244	615.8	102.6	586.5	
MED	187+91.78	189+45.00	153.2				5.0	5.0	85	85		35	93.6	15.6	85.1	
	SUB-TOTAL		1,374.3						1,352	1,352		563	1,427.9	238.0	1,351.6	
SOUTHBOUND	OUT	44+00.00	47+60.00	360.0				4.0	10.0	280	280			300.0	50.0	280.0
	OUT	47+60.00	52+57.49	497.5				10.0	10.0	553	553			580.4	96.7	552.8
	OUT	52+57.49	93+86.98	4,129.5				10.0	10.0	4,588	4,588			4,817.7	803.0	4,588.3
		SUB-TOTAL		4,987.0						5,421	5,421		***	5,698.1	949.7	5,421.1
	MED	110+65.00	110+75.00	10.0	25.0	25.0	28				28	9		28	5	27.8
	MED	110+75.00	110+92.00	17.0	37.3	37.3	70				70	11		70	12	70.4
	MED	110+92.00	111+27.50	35.5	50.0	50.0	197				197	21		197	33	197.2
	MED	111+27.50	112+94.47	167.0	38.0	38.0	705	5.0	5.0	93	798	8		807	135	797.7
	MED	112+94.47	115+02.47	208.0	38.0	12.0	578	5.0	5.0	116	693			705	117	693.3
	MED	115+02.47	117+50.00	247.5	12.0	12.0	330	5.0	5.0	138	468			481	80	467.6
	MED	117+50.00	118+00.00	50.0	12.0	0.0	33	5.0	5.0	28	61			64	11	61.1
		SUB-TOTAL		735.0			1,941			374	2,315	49	***	2,352.5	392.1	2,315.1
	MED	119+23.00	120+43.00	120.0	9.5	2.0	77	5.0	5.0	67	143			150.1	25.0	143.4
	MED	120+43.00	120+75.00	32.0	14.0	12.0	46	5.0	5.0	18	64	36		65.8	11.0	64.0
	MED	120+75.00	122+50.00	175.0	12.0	12.0	233	5.0	5.0	97	331	24		340.3	56.7	330.6
	MED	122+50.00	123+00.00	50.0	12.0	0.0	33	5.0	5.0	28	61			63.9	10.6	61.1
	OUT	119+25.00	123+24.71	399.7				10.0	10.0	444	444			466.3	77.7	444.1
	MED	126+36.38	128+74.00	237.6				10.0	10.0	264	264			277.2	46.2	264.0
	MED	126+61.38	128+00.00	138.6				5.0	5.0	77	77			84.7	14.1	77.0
	MED	128+00.00	128+53.00	53.0	0.0	8.7	26	5.0	5.0	29	55			58.0	9.7	55.1
OUT	126+40.23	126+65.23	25.0				10.0	10.0	28	28			29.2	4.9	27.8	
OUT	126+65.23	128+76.00	210.8	12.0	7.7	231	10.0	10.0	234	465	140		476.9	79.5	465.2	
	SUB-TOTAL		1,441.7			646			1,286	1,932	200	***	2,012.4	335.4	1,932.3	
OUT	181+25.00	187+23.85	598.8				10.0	10.0	665	665		277	698.7	116.4	665.4	
MED	185+45.00	187+04.22	159.2				5.0	5.0	88	88		37	97.3	16.2	88.5	
MED	188+23.53	189+80.00	156.5				5.0	5.0	87	87		36	95.6	15.9	86.9	
OUT	188+40.27	193+00.00	459.7				10.0	10.0	511	511		213	536.4	89.4	510.8	
	SUB-TOTAL		1,374.3						1,352	1,352		563	1,427.9	238.0	1,351.6	
SHEET TOTAL											397	1,126	22,536	3,756	21,605	

\*\*\* SEE SHEET 65 FOR QUANTITIES

PAVEMENT WORK QUANTITIES FOR S.R. 44

LAK-44-0.01

63  
196

CALCULATED  
NRE  
CHECKED  
XXX

PLOT SUBMITTED: 10-FEB-1999 11:11  
PLOTTED BY: jgrnovse  
PLOTTED FROM: I:\PROJECTS\p1d\098666\098666gsf.dgn

098666gsf.dgn