

PLOT SUBMITTED: 05-FEB-1999 10:10

26

PLOTTED BY: fkonopka
 PLOTTED FROM: i:\projects\pic09866\09866tsf.dgn

SHEET NO.	REFERENCE NO.	ELEVATION VIEW SHEET NO.	LOCATION				CODE	SIZE	630															
			ROUTE	DIRECTION	STATION	SIDE			GROUND MOUNTED SUPPORT, S4X7.7 BEAM	GROUND MOUNTED SUPPORT, W6X9 BEAM	GROUND MOUNTED SUPPORT, W10X22 BEAM	GROUND MOUNTED SUPPORT, W10X12	GROUND MOUNTED SUPPORT, W12X30	GROUND MOUNTED SUPPORT NO. 3 POST	BREAKAWAY BEAM CONNECTION	SIGN, FLAT SHEET, TYPE G	SIGN, EXTRUSHEET, TYPE G	GROUND MOUNTED BEAM SUPPORT FOUNDATION	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	REMOVAL OF GROUND MOUNTED SIGN AND REECTION	REMOVAL OF GROUND MOUNTED BEAM SUPPORT AND DISPOSAL			
								LIN FT	LIN FT	LIN FT	LIN FT	LIN FT		EACH	SQ FT	SQ FT	EACH	EACH	EACH	EACH				
151	100A	162	SR-44	NB	78+50	RT.	8' X7'					26.5	28.1			2	56	2						
151	101A	162	SR-44	NB	86+32	RT.	13' X5.5'					21	21.8			2	71.5	2	1		2			
154	102A	162	SR-44	NB	144+00	RT.	15' X12'							32	36.5		180	2						
154	103A	162	SR-44	SB	149+00	RT.	13' X5.5'					21	21.8					2		1	2			
154	104A		SR-44	NB	149+50	RT.												2			2			
156	105	163	SR-44	NB	160+00	RT.	GHS-120 8' X4'		17.2	18							32	2	1		2			
156	106	163	SR-44	SB	161+60	RT.	8' X7'					22.5	23.1				56	2			2			
156	107	163	SR-44	NB	168+50	RT.	19' X7'			24.3	19.8						133	2						
156	108	163	SR-44	NB	177+00	RT.	15' X12'							30.8	29.1		180	2						
157	109		SR-44	NB	182+85	RT.												2		1	2			
158	110	164	RAMP "C"	NB	16+00	RT.	M-2-24-2 2' X2'					20.3	23.3		12		4	2						
							M-25-21 21" X15"										2.2							
							M-8-24 2' X1'										2							
							M-1-24-2 2' X2'										4							
							M-24-21 21" X15"										2.2							
							11' X4'										44							
158	111	164	RAMP "C"	NB	20+00	RT.	N-29-24 2' X2'		23.5	19.2					6		4	2						
							N-15-24 2' X6"										1							
							12' X4'										48							
161	112	164	SR-84	WB	19+25	RT.	M-52A-108 9' X2.5'	14.3	14								22.5	2						
161	113	164	SR-84	EB	0+35	RT.	M-52A-108 9' X2.5'	14.3	14								22.5	2						
SUB-TOTALS								57	78	55	230	129	18	4	51.4	768.5	24	4	1	10				

CALCULATED KAS	CHECKED FLK	BEAM MOUNTED SIGN SUB-SUMMARY