

PLOTTED BY: fkonopka
 PLOTTED FROM: \\projects\p\d09866\lga.dgn
 PLOT SUBMITTED: 10-FEB-1999 06:05
 09866.lga.dgn

SHEET NUMBER				PARTICIPATION			ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
	190		192		193							
			4			202	75300	4	EACH	PULL BOX REMOVED		
			13			202	75400	13	EACH	LIGHT POLE REMOVED		
			13			202	75500	13	EACH	LIGHT POLE FOUNDATION REMOVED		
			14			202	75506	14	EACH	LUMINAIRE REMOVED		
			2			202	75801	2	EACH	DISCONNECT EXISTING CIRCUIT, AS PER PLAN	190	
			1			202	98100	1	EACH	REMOVAL MISC.: BRACKET ARM REMOVED AND REERECTED		
					75	603	00400	75	LIN FT	4" CONDUIT, TYPE E		
					21	625	00500	21	EACH	CONNECTOR KIT, TYPE II		
					21	625	00600	21	EACH	CONNECTOR KIT, TYPE III		
					20	625	01500	20	EACH	CABLE SPLICING KIT		
					17	625	04400	17	EACH	LIGHT POLE, DESIGN AT15B34.2		
					8	625	14000	8	EACH	LIGHT POLE FOUNDATION, 24" X 6' DEEP		
					9	625	14100	9	EACH	LIGHT POLE FOUNDATION, 24" X 8' DEEP		
					1760	625	23400	1760	LIN FT	NO. 10 AWG POLE AND BRACKET CABLE		
					3629	625	24100	3629	LIN FT	1-1/2" DUCT CABLE WITH TWO NO. 4 AWG 5000 VOLT CABLES		
					193	625	25900	193	LIN FT	CONDUIT, JACKED OR DRILLED, 3"		
					9	625	26250	9	EACH	LUMINAIRE, CONVENTIONAL, 200 W. HPS, TYPE III, 480 VOLT		
					9	625	26250	9	EACH	LUMINAIRE, CONVENTIONAL, 200 W HPS, TYPE II, 480 VOLT		
					3166	625	29002	3166	LIN FT	TRENCH, 24" DEEP		
					7	625	30700	7	EACH	PULL BOX, 713.08, 18"		
					17	625	32000	17	EACH	GROUND ROD		
	LUMP					SPECIAL	62540000	LUMP		MAINTAIN EXISTING LIGHTING	190	
		LUMP				690	71000	LUMP		ASBESTOS ABATEMENT	190	

CALCULATED BJK
 CHECKED ENF
 LIGHTING GENERAL SUMMARY
 LAK-44-0.01
 191
 196