



RAMP "B" NOT INCLUDED  
IN PROJECT F-388(10)

**ESTIMATED QUANTITIES**

ITEM	DESCRIPTION	QUANTITY
B-219	3" WATERPROOFED AGGREGATE BASE COURSE (TYPE "B")	150.33 CU.YD.
I-12	CONCRETE CURB, SPECIAL (SEE DETAIL-SH. 112)	628.06 LIN.FT.
I-18	STABILIZED CRUSHED AGGREGATE SHOULDERS & APPROACHES	257.67 CU.YD.
I-22	SUBBASE	531.41 CU.YD.
T-31	BITUMINOUS SURFACE TREATMENT	1803.94 SQ.YD.
T-71	9" REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT	1838.58 SQ.YD.

**GENERAL NOTES FOR RAMPS**  
SEE SHEET NO. 132  
**JOINT SYMBOLS**  
SEE SHEET NO. 132

TRYGVE HOFF & ASSOCIATES  
ENGINEERS  
1922 EAST 107TH STREET CLEVELAND, OHIO

**RAMP "B"**  
**PAVEMENT**      **DETAILS**

SCALE 1"=20'      DATE

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
GOH	OC		O.M.F.	T.L.L.	10/11/58	