

PLOTTED FROM: I:\PROJECTS\Pad18391\dgn\18391qga.dgn

PAVEMENT PLANING AND RESURFACING QUANTITIES													
STATION		LENGTH LIN FT	RESURFACING END WIDTHS (AVG.) LIN FT	RESURFACING SURFACE AREA SQ YD	202			858			407		REMARKS
FROM	TO				WEARING COURSE REMOVED, AS PER PLAN	1-1/2" ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	3-1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446)	2" ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446)	TACK COAT	TACK COAT FOR INTERMEDIATE COURSE			
SR-44 NORTHBOUND													
232+25.00	233+00.00	75.00	49.7	414	414	19	17	41	14	1-1/2" TO 5" OVERLAY			
233+00.00	237+10.00	410.00	43.4	1977	1815	82	192	198	99				
237+10.00	270+30.00	3320.00	38	14018	12542	584	1363	1402	701				
270+30.00	270+80.00	50.00	38	211	189	9	15	21	10	5" TO 3" OVERLAY			
270+80.00	272+20.00	140.00	38	591	529	25	25	59	29	3" OVERLAY			
272+20.00	272+70.00	50.00	38	211	189	9	15	21	10	3" TO 5" OVERLAY			
272+70.00	294+30.00	2160.00	38	9120	8160	380	887	912	456				
294+30.00	297+00.00	270.00	67	2010	1680	84	195	201	100	RAMP WIDENING			
297+00.00	307+00.00	1000.00	50.6	5622	5178	234	547	562	281				
307+00.00	308+97.83	197.83	38	835	747	35	81	84	42				
308+97.83	309+85.33	87.50	38	369	331	17	17	37	13	5" TO 1-3/4" OVERLAY			
309+85.33	310+14.33	29.00	14	45	45	2		5		1-3/4" OVERLAY ON SHOULDERS			
BRIDGE NO. LAK-44-0561 R													
312+38.33	312+45.00 BK=	6.67	14	10	10	1		1		1-3/4" OVERLAY ON SHOULDERS			
RAMP G													
0+00.00 AH	0+22.33	22.33	14	35	35	2		4		1-3/4" OVERLAY ON SHOULDERS			
0+22.33	1+09.83	87.50	38	369	331	17	17	37	13	1-3/4" TO 5" OVERLAY			
1+09.83	18+00.00	1690.17	38	7136	6385	297	694	714	357				
18+00.00	18+40.00	40.00	38	169	169	7	13	17	9	5" TO 3-1/2" OVERLAY			
18+40.00	19+81.87	141.87	38	599	599	25		33	60	30			
19+81.87	22+70.00	288.13	52.5	1681	1681	70		93	168	84			
22+70.00	29+33.76	663.76	31	2286	2286	95	127	229	114				
29+33.76	29+83.76	50.00	31	172	172	8		4	17	4	3-1/2" TO 1-1/2" OVERLAY		
BRIDGE NO. LAK-2-1354 ES													
33+03.27	33+53.27	50.00	31	172	172	8		4	17	4	1-1/2" TO 3-1/2" OVERLAY		
33+53.27	44+20.54	1067.27	31	3676	3676	153		204	368	184			
RAMP F													
2+65.69	15+55.00	1289.31	31	4441	4441	185		247	444	222			
SR-44 SOUTHBOUND													
232+25.00	233+00.00	75.00	48	400	400	19	17	40	13	1-1/2" TO 5" OVERLAY			
233+00.00	233+28.95	28.95	48	154	141	6	15	15	8				
233+28.95	234+28.95	100.00	43	478	433	20	46	48	24				
234+28.95	294+80.64	6051.69	38	25552	22862	1065	2484	2555	1278				
294+80.64	298+00.00	319.36	56	1987	1632	83	193	199	99	RAMP WIDENING			
298+00.00	299+00.00	100.00	47.5	528	483	22	51	53	26				
299+00.00	301+81.00	281.00	48	1499	1374	62	146	150	75				
301+81.00	302+81.00	100.00	43	478	434	20	46	48	24				
302+81.00	308+97.83	616.83	38	2604	2330	109	253	260	130				
308+97.83	309+85.33	87.50	38	369	331	17	17	37	13	5" TO 1-3/4" OVERLAY			
309+85.33	310+14.33	29.00	14	45	45	2		5		1-3/4" OVERLAY ON SHOULDERS			
BRIDGE NO. LAK-44-0561 L													
312+38.33	312+45.00 BK=	6.67	14	10	10	1		1		1-3/4" OVERLAY ON SHOULDERS			
RAMP E													
46+75.63	46+97.96 AH	22.33	14	35	35	2		4		1-3/4" OVERLAY ON SHOULDERS			
45+88.13	46+75.63	87.50	38	369	331	17	17	37	13	1-3/4" TO 5" OVERLAY			
29+00.00	45+88.13	1688.13	38	7128	6377	297	639	713	356				
28+60.00	29+00.00	40.00	38	169	169	7	13	17	9	3-1/2" TO 5" OVERLAY			
28+08.43	28+60.00	51.57	38	218	218	9		12	22	11			
25+09.44	28+08.43	298.99	53	1761	1761	73		98	176	88			
TOTAL (LEFT SIDE)					91142	4179	8015	822	9999	4943			

ASPHALT TRANSITION (SEE ASPHALT TRANSITION DETAIL, SHEET 52.)

PAVEMENT PLANING AND RESURFACING QUANTITIES													
STATION		LENGTH LIN FT	RESURFACING END WIDTHS (AVG.) LIN FT	RESURFACING SURFACE AREA SQ YD	202			858			407		REMARKS
FROM	TO				WEARING COURSE REMOVED, AS PER PLAN	1-1/2" ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	3-1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446)	2" ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446)	TACK COAT	TACK COAT FOR INTERMEDIATE COURSE			
RAMP E													
18+66.20	25+09.44	643.24	31	2216	2216	92	123	222	111				
18+16.20	18+66.20	50.00	31	172	172	8	4	17	4	1-1/2" TO 3-1/2" OVERLAY			
BRIDGE NO. LAK-44-0620 SW													
13+74.44	14+24.44	50.00	31	172	172	8	4	17	4	3-1/2" TO 1-1/2" OVERLAY			
2+70.00	13+74.44	1104.44	31	3804	3804	159	211	380	190				
RAMP H													
2+95.97	13+65.00	1069.03	31	3682	3682	153	204	368	184				
RAMP I													
4+18.56	5+18.56	100.00	26.5	294	222	12	29	29	14	RAMP WIDENING			
5+18.56	7+05.00	186.44	25	518	394	22	50	52	52	RAMP WIDENING			
RAMP 2													
2+69.41	12+69.09	999.68	25	2777	2110	116	270	278	139	RAMP WIDENING			
12+69.09	12+83.24	14.15	22	35	35	1	3	4	2				
12+83.24	13+58.24	75.00	CADD	286	286	14	8	29	6	5" TO 1-1/2" OVERLAY			
SR-2 EASTBOUND													
585+72.12	586+22.12	50.00	39	217	217	11	5	22	5	1-1/2" TO 3-1/2" OVERLAY			
586+22.12	593+92.50	770.38	39	3338	3338	139	185	334	167				
593+92.50	594+92.50	100.00	45	500	500	21	28	50	25				
594+92.50	599+23.72	431.22	51	2444	2444	102	136	244	122				
599+23.72	601+92.50	268.78	63.5	1896	1896	79	105	190	95				
601+92.50	622+32.00	2039.5	39	8838	8838	368	491	884	442				
622+32.00	625+00.00	268.00	63.5	1891	1891	79	105	189	95				
625+00.00	628+38.84	338.84	51	1920	1920	80	107	192	96				
628+38.84	633+60.22	521.38	40	2317	2317	97	129	232	116				
633+60.22	657+25.10	2364.88	39	10248	10248	427	569	1025	513				
657+25.10	657+75.10	50.00	39	217	217	11	5	22	5	3-1/2" TO 1-1/2" OVERLAY			
SR-2 WESTBOUND													
585+72.12	586+22.12	50.00	39	217	217	11	5	22	5	1-1/2" TO 3-1/2" OVERLAY			
586+22.12	588+99.53	277.41	39	1202	1202	50	67	120	60				
588+99.53	594+20.91	521.38	45	2607	2607	109	145	261	130				
594+20.91	597+59.75	338.84	51	1920	1920	80	107	192	96				
597+59.75	600+31.00	271.25	63.5	1914	1914	80	106	191	95				
600+31.00	625+54.50	2523.50	39	10935	10935	456	608	1094	547				
625+54.50	628+23.28	268.78	63.5	1896	1896	79	105	190	95				
628+23.28	632+54.50	431.22	51	2444	2444	102	136	244	122				
632+54.50	633+54.50	100.00	45	500	500	21	28	50	25				
633+54.50	657+25.10	2370.60	39	10273	10273	428	571	1027	513				
657+25.10	657+75.10	50.00	39	217	217	11	5	22	5	3-1/2" TO 1-1/2" OVERLAY			
TOTAL (THIS SIDE)					81044	3426	360	4294	8193	4080			
TOTAL (LEFT SIDE)					91142	4179	8015	822	9999	4943			
TOTAL TO GENERAL SUMMARY					172186	7605	8375	5116	18192	9023			

RESURFACING QUANTITIES

LAKE COUNTY  
LAK-2/44-13.05/4.14