

I:\PROJECTS\PI\018391\B&N\PLANS\2136560.DGN 14-AUG-2001 12:55PM fkomopka

REF NO.	SHEET NO.	STATION		SIDE	202					203				254	202	301	304	305	407		CALCULATED	CHECKED
					PAVEMENT REMOVED	CATCH BASIN REMOVED	CATCH BASIN ABANDONED	GUARDRAIL REMOVED	CURB REMOVED	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	EMBANKMENT	SUBGRADE COMPACTION	LINEAR GRADING	PAVEMENT PLANING, BITUMINOUS, 1.25"	WEARING COURSE REMOVED, AS PER PLAN	7" BITUMINOUS AGGREGATE BASE, PG64-22	6" AGGREGATE BASE, AS PER PLAN	9" CONCRETE BASE, AS PER PLAN	TACK COAT @ 0.1 GAL/SQ.YD.	TACK COAT FOR INTERMEDIATE COURSE @ 0.05 GAL/SQ.YD.		
					SQ. YD.	EACH	EACH	LIN. FT.	LIN. FT.	CU. YD.	CU. YD.	SQ. YD.	STA.	SQ. YD.	SQ. YD.	CU. YD.	CU. YD.	SQ. YD.	GAL.	GAL.		
		JACKSON STREET																				
		6+40.00	7+62.00					123		21			2		7		6	32	3	2		
		8+57.00±	8+73.00±					15		5			1				2	7	1	1		
		11+12.00±	11+20.00±					12		3			1				1	5	1	1		
		12+11.93	13+50.00					23		21			2				6	32	3	2		
		8+73.00	8+86.00±																			
		10+99.00	11+12.00±																			
		FERN DRIVE																				
		6+50.00	7+75.00					23		55		94	2	334		5	15		42	5		
		7+75.00	8+64.00±					38	3	48		77	2			12	12	71	24	12		
		8+17.00	8+64.00±											44								
		RAMP 1																				
		7+05.00	7+50.00									41			95		6	33	13	7		
		7+50.00	12+25.00									753			1002		117	674	168	84		
		12+25.00	14+05.00			1	1					545			381		88	514	90	45		
		14+05.00	14+68.00									63			155		25	144	31	16		
		14+68.00	15+25.00±				37.50					88			263		14	72	34	17		
		7+05.00	15+25.00±									432	1479									
TOTALS CARRIED TO GENERAL SUMMARY					84	4	1	37.50	681	585	1479	1711	10	380	1903	17	292	1584	410	192		

ESTIMATED QUANTITIES
 LAKE COUNTY
 LAK-2/44-13.05/4.14
 50C
 93