

\$FILE\$ I:\PROJECTS\PI\B39\B&N\PLANS\B39\ISSA.DGN 09-NOV-2001 12:28PM fkomopk.d

ESTIMATED QUANTITIES							AS PER PLAN REFERENCE SHEET NO.
ITEM	ITEM EXT.	NHS	STP	TOTAL	UNIT	DESCRIPTION	
202	11201	LUMP		LUMP		PORTIONS OF STRUCTURE REMOVED, AS PER PLAN	2 / 8
SPECIAL	512E67510	182		182	SQ. YD.	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) *	
514	27700	50		50	SQ. FT.	FIELD PAINTING, MISC.: JOINT ARMOR	
516	01300	13		13	LIN. FT.	ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS	
516	11900	13		13	LIN. FT.	HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT	
517	76201	216		216	LIN. FT.	RAILING FACED, AS PER PLAN	3 / 8
607	35000	216		216	LIN. FT.	FENCE REMOVED AND REBUILT	
842	81300	10		10	EACH	CONCRETE, MISC.: DRILLING AND GROUTING DOWEL HOLES**	
842	81400	50		50	POUNDS	CONCRETE, MISC.: REPLACEMENT OF EXISTING REINFORCING STEEL**	
844	49500	12		12	CU. YD.	HIGH PERFORMANCE CONCRETE MISC.: DECK AND APPROACH SLAB EXTENSION, AS PER PLAN	3 / 8
847	10000	138		138	SQ. YD.	MICROSILICA MODIFIED CONCRETE OVERLAY (1 3/4" THICKNESS)	
847	20000	2		2	CU. YD.	MICROSILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS) **	

* SEE PROPOSAL NOTE
 ** CONTINGENCY QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER

DESIGN AGENCY
 BURGESS & NIPLE
 100 WEST ERIE STREET PAINESVILLE, OHIO 44077

DATE 2-28-01
 REVIEWED DWL
 STRUCTURE FILE NUMBER 4302702
 DRAWN MKB
 DESIGNED MKB
 CHECKED SCT

ESTIMATED QUANTITIES
 BRIDGE NO. LAK-44-0510
 JACKSON STREET OVER STATE ROUTE 44

LAKE COUNTY
 LAK-2/44-13.05/4.14
 4 / 8
 85D
 93