

GENERAL SUMMARY

LAKE COUNTY
LAK-44-2.02
LAK-90-14.68

15
47

PLAN NO.

COMPUTED BY: L.D. 12-76
CHECKED BY: F.K. 12-76

Type Code 6706, unless otherwise shown

ITEM	SHEET NUMBER										PARTICIPATION		GRAND TOTAL	ITEM	UNIT	DESCRIPTION
	4	10	24	42												
											1					TRAFFIC (CONTINUED)
847										4.34	4.34	4.34	847	MILES	6" TEMPORARY LANE LINE, 847.12	
847										220	220	220	847	LIN.FT.	4" TEMPORARY CENTER LINE (DOUBLE YELLOW), 847.12	
847										2080	2080	2080	847	LIN.FT.	8" TEMPORARY CHANNELIZING LINE, 847.12	
847										45	45	45	847	LIN FT	24" TEMPORARY STOP LINE, 847.12	
																DRAINAGE
603										362	362	362	603	LIN.FT.	15' CONDUIT, TYPE "C"	
604										1	1	1	604	EACH	STD. NO. 2-2-B CATCH BASIN, STD. No. 2-2-B	
604										2	2	2	604	EACH	STD. NO. 2-2-A CATCH BASIN RECONSTRUCTED TO GRADE	
605												180	605	Lin.Ft.	AGGREGATE DRAINS <i>new relief st.</i>	
605												110	605	Lin.Ft.	AGGREGATE DRAINS, AS PER PLAN <i>as attached</i>	
																FOR BRIDGE QUANTITIES, SEE SHEET NO 34
619													LUMP	619		FIELD OFFICE
623													LUMP	623		CONSTRUCTION LAYOUT STAKES
614													LUMP	614		MAINTAINING TRAFFIC

PARTICIPATION CODES: 1- U-62(3) 30% STATE & 70% FEDERAL
2- I-90-1(107)58 10% STATE & 90% FEDERAL