

PAVEMENT MARKINGS																		
ROADWAY	STATION		SIDE L OR R	ITEM 621										ITEM 847.2 (TEMPORARY)				
				4" EDGE LINE (WHITE)	4" EDGE LINE (YELLOW)	6" LANE LINE	4" LANE LINE	4" CENTER LINE (DOUBLE YELLOW)	8" CHANNELIZING LINE	24" BROAD TRANSVERSE LINE	24" STOP LINE	LANE ARROW	6" TEMPORARY LANE LINE	4" TEMPORARY CENTER LINE (DOUBLE YELLOW)	8" TEMPORARY CHANNELIZING LINE	24" TEMPORARY STOP LINE		
				MILES	MILES	MILES	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	MILES	LIN. FT.	LIN. FT.	LIN. FT.	
S.R.44	122+35	237+10*	L	2.17	2.17	2.17				330	65				2.17		330	
S.R.44	122+35	237+10*	R	2.17	2.17	2.17	50					41			2.17			
RAMP A	0+26	8+22.70	L&R	0.15	0.15							45	1					
RAMP A	8+22.70	10+00	L&R						650	160							650	
RAMP A	10+00	13+40.83	L&R				341											
RAMP B	0+26	9+25	L&R	0.17	0.17													
RAMP B	9+25	12+65.77	L&R	0.07					240								240	
RAMP C	4+40	8+30	L&R				390											
RAMP C	8+80	13+01.93	L&R						660	160							660	
RAMP C	13+01.93	23+49.59	L&R	0.17	0.17							45	1					
RAMP D	8+50	11+08.21	L&R				259											
RAMP D	11+08.21	13+08.21	L&R	0.04					200								200	
RAMP D	13+08.21	23+00†	L&R	0.20	0.10							54						
RAMP D	23+00	25+51†	L&R	0.08	0.05			220				45	2		220		45	
TOTALS				5.22	4.98	4.34	1040	220	2080	385	230	4			4.34	220	2080	45

DELINEATORS				
ROADWAY	TYPE "A"	TYPE "A"	TYPE "D"	TYPE "D"
	POST MOUNTED	BRACKET MOUNTED	POST MOUNTED	BRACKET MOUNTED
	EACH	EACH	EACH	EACH
MAINLINE	88	3	11	3
RAMP "A"			19	
RAMP "B"			22	
RAMP "C"			28	
RAMP "D"			25	
TOTALS	88	3	105	3

* INCLUDING 1-90 & S.R.44 RAMPS
† INCLUDING MORLEY ROAD
FOR DELINEATOR LOCATIONS, SEE SHEETS 16 to 21

FOR DETAILS, SEE SHEET No 43