FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

15
204

LAKE COUNTY
LAK 44-3.79

GENERAL SUMMARY

SHEET NUMBER			ITEM	TOTAL U-388(12) MUNICIPAL	TOTAL UG-388(12) MUNICIPAL	TOTAL FG-388(12)	GRAND TOTAL	UNIT	DESCRIPTION
U-388(12) MUNY	141	142	146						
									BUILDING REMOVALS (CODE 7221)
			E-10		LUMP		LUMP SUM	LUMP	REMOVAL OF 1-STORY BRICK AND CONCRETE BLOCK BUILDING AND 1-STORY CONCRETE BLOCK BUILDING, PARCEL No. 49 LA
			E-10		LUMP		LUMP SUM	LUMP	REMOVAL OF 3-CAR SHEET METAL GARAGE, SHEET METAL SHED, STEEL LOADING PLATFORM, AND 4 STEEL STORAGE TANKS, (PARCEL No 50 LA)
			E-10		LUMP		LUMP SUM	LUMP	REMOVAL OF 1-STORY CONCRETE BLOCK GAS STATION, 1-500 GAL. AND 2-2000 GAL. UNDERGROUND GASOLINE TANKS, PARCEL No. 50A-LA
			E-10		1		1	EACH	REMOVAL OF 1-STORY CONCRETE BLOCK BUILDING, PARCEL No. 52 LA
			E-10		1		1	EACH	REMOVAL OF 1½-STORY FRAME DWELLING, PARCEL No. 59 LA.
			E-10		1		1	EACH	REMOVAL OF 1-STORY SHEET METAL GAS STATION, PARCEL No. 67 LA
			E-10		LUMP		LUMP SUM	LUMP	REMOVAL OF 2½-STORY FRAME DWELLING, 3-CAR FRAME GARAGE, FRAME SHED, AND HOUSE TRAILER, PARCEL No. 68 LA.
			E-10		LUMP		LUMP SUM	LUMP	REMOVAL OF TWO 1½-STORY FRAME DWELLINGS AND 2-CAR FRAME GARAGE, PARCEL No. 71 LA.
			E-10	LUMP			LUMP SUM	LUMP	REMOVAL OF 2½-STORY FRAME DWELLING, 2½-STORY FRAME 3-CAR GARAGE WITH ATTACHED SHED AND TWO FRAME CHICKEN HOUSES, PARCEL No. 83 LA
			E-10	LUMP			LUMP SUM	LUMP	REMOVAL OF 2½-STORY FRAME DWELLING AND 1½-STORY FRAME GARAGE, PARCEL No. 86 LA
			E-10			2	2	EACH	REMOVAL OF FRAME SHEDS, PARCEL № 93LA.
									STRUCTURES OVER 20 FT. SPAN
									LAK.44-0483 FOR ESTMATED QUANTITIES, SEE SHEET № 156
									LAK.44-0489 FOR ESTIMATED QUANTITIES, SEE SHEET № 171
									LAK.44-0505 FOR ESTIMATED QUANTITIES, SEE SHEET № 180
									LAK.44-0556 L&R., FOR ESTIMATED QUANTITIES, SEE SHT. № 187
									WATER MAINS (CODE Y-060)
10			I-124	10			10	LIN. FT.	6" NEW CAST IRON WATER MAIN.
	196		I-124	196			196	LIN. FT.	8" NEW CAST IRON WATER MAIN
220			I-124	220			220	LIN. FT.	10" NEW CAST IRON WATER MAIN
	124		I-124	124			124	LIN. FT.	8" NEW CAST IRON WATER MAIN, CLASS 200.
122			I-124	122			122	LIN. FT.	10" NEW CAST IRON WATER MAIN, CLASS 200.
473			I-124	473			473	LIN. FT.	INSTALL 6" CAST IRON WATER MAIN AND FITTINGS, AS PER PLAN
473			I-124	473			473	LIN. FT.	REMOVE, CLEAN AND STORE 6" CAST IRON WATER MAIN AND FITTINGS AS PER PLAN
	4		I-124	4			4	EACH	8" CAST IRON FITTINGS, 1/8 BEND.
	3		I-124	3			3	EACH	8" CAST IRON FITTINGS, 1/16 BEND.
	2		I-124	2			2	EACH	CAST IRON FITTINGS, 8" × 6" REDUCER
4			I-124	4			4	EACH	10" CAST IRON FITTINGS, 1/8 BEND
4			I-124	4			4	EACH	10" CAST IRON FITTINGS, 1/16 BEND
2			I-124	2			2	EACH	CAST IRON FITTINGS, 10" × 6" REDUCER
1			I-124	1			1	EACH	CAST IRON FITTING, 10" × 6" WYE
1			I-124	1			1	EACH	CAST IRON FITTING, 10" × 6" TEE
1			I-124	1			1	EACH	6" GATE VALVE AND VALVE BOX
	2		I-124	2			2	EACH	8" GATE VALVE AND VALVE BOX
2			I-124	2			2	EACH	10" GATE VALVE AND VALVE BOX
									SANITARY SEWERS (CODE Y-060)
	18		I-124	18			18	LIN. FT.	3/4" STEEL PIPE, SEC. M-6.9, CORROSION PROTECTED, AS PER PLAN
	290		I-124	290			290	LIN. FT.	6" CAST IRON SANITARY SEWER WITH MECHANICAL JOINTS
	124		I-124	124			124	LIN. FT.	6" CAST IRON SANITARY SEWER, CLASS 200, WITH MECHANICAL JTS.
	2		I-124	2			2	EACH	6" CAST IRON FITTINGS, 1/4 BEND
	1		I-124	1			1	EACH	6" CAST IRON FITTING, 1/8 BEND
	4		I-124	4			4	EACH	6" CAST IRON FITTINGS, 1/16 BEND
	2		I-8	2			2	EACH	REBUILD SANITARY MANHOLES, AS PER PLAN
	LUMP		SPECIAL	LUMP			LUMP SUM	LUMP	DUPLEX PNEUMATIC EJECTOR SEWAGE LIFT STATION
									ELECTRICAL (CODE Y-060)
		66	S-25	66			66	LIN. FT.	1-3" DUCT, CONCRETE ENCASED
		54	S-25	54			54	LIN. FT.	1-4" DUCT, CONCRETE ENCASED
		18	S-25	18			18	LIN. FT.	1-3" & 1-4" DUCTS, CONCRETE ENCASED
		280	S-25	280			280	LIN. FT.	1-3" & 2-4" DUCTS, CONCRETE ENCASED
		155	S-25	155			155	LIN. FT.	1-3" & 3-4" DUCTS, (TYPE "A") CONCRETE ENCASED
		20	S-25	20			20	LIN. FT.	1-3" & 3-4" DUCTS, (TYPE "B") CONCRETE ENCASED
		4	I-8	4			4	EACH	ELECTRICAL MANHOLES, AS PER PLAN.
		1	I-8	1			1	EACH	PULL BOX MANHOLE, AS PER PLAN.