

STREAM CHANNEL EXCAVATION

THE CONTRACTOR SHALL TAKE ALL THE PRECAUTIONS NECESSARY TO PREVENT ANY INCIDENTAL DISCHARGES ASSOCIATED WITH THE EXCAVATION AND HAULING OF MATERIAL FROM THE STREAM CHANNEL. THIS PERTAINS TO ANY EXCAVATION OPERATIONS SUCH AS, FOUNDATION PIER OR ABUTMENT EXCAVATION, CHANNEL CLEAN OUT, EXCAVATION FOR ROCK CHANNEL PROTECTION AND REMOVAL OF ANY TEMPORARY FILL ASSOCIATED WITH CONSTRUCTION OPERATIONS.

DEMOLITION DEBRIS

THE CONTRACTOR SHALL TAKE PRECAUTIONS TO AVOID AND/OR LIMIT DEMOLITION DEBRIS FROM ENTERING THE STREAM. ANY MATERIAL THAT DOES FALL INTO THE STREAM SHALL BE REMOVED AS SOON AS POSSIBLE.

INSTREAM WORK

INSTREAM WORK WILL BE LIMITED WHERE PRACTICABLE AND ONLY CLEAN NON-ERODIBLE MATERIAL WILL BE USED FOR FORDS OR COFFERDAMS. THIS TEMPORARY PLACED MATERIAL WILL BE REMOVED AND THE STREAM BOTTOM RESTORED TO NEAR NATURAL CONDITIONS WHEN THE WORK IS COMPLETED

ITEM 304 - AGGREGATE BASE, AS PER PLAN

THE ONLY SLAG MATERIALS PERMITTED FOR THIS ITEM SHALL BE CRUSHED AIR-COOLED BLAST FURNACE SLAG, A MIXTURE OF CRUSHED AND GRANULATED SLAGS, OR OPEN HEARTH SLAG FROM APPROVED SOURCES ON FILE AT THE LABORATORY.

ALL MATERIALS OR BLENDED MATERIALS SHALL MEET THE GRADATION REQUIREMENTS OF 304.02.

ANY GRANULATED SLAG MATERIAL USED SHALL MEET THESE GRADATION REQUIREMENTS IN LIEU OF 703.08.

CALCULATED
JC
CHECKED
NT

GENERAL NOTES

LAK - 528 - 8.095

4A
33