

MAINTENANCE OF TRAFFIC SUB-SUMMARY					
	PHASE I	SUBTOTAL	PHASE II	SUBTOTAL	TOTAL*
ITEM 614- BARRIER REFLECTOR, TYPE B (WHITE)	STA. 8+082.284 TO STA. 8+126.086, 45.80 m/7.6 + 1 = 7 EACH	7	STA. 8+082.284 TO STA. 8+110.861, 30.50 m/7.6 + 1 = 5 EACH	5	12 EACH
ITEM 614- OBJECT MARKER	STA. 8+082.284 TO STA. 8+126.086, 45.80 m/7.6 + 1 = 7 EACH	7	STA. 8+082.284 TO STA. 8+110.861, 30.50 m/7.6 + 1 = 5 EACH	5	12 EACH
ITEM 615- TEMPORARY PAVEMENT, CLASS A	STA. 8+072.000 TO STA. 8+090.525, 18.525 m STA. 8+107.475 TO STA. 8+120.000, 12.525 m 31.05 m X 0.91 m = 28.26 sq m	28.26			28.26 sq m, USE 28 sq m
ITEM 614- TEMPORARY EDGE LINE, CL. I, 740.06, TYPE I	STA. 8+042.000 TO STA. 8+149.000, 0.15 X 2 = 0.30 km	0.30	STA. 8+042.000 TO STA. 8+149.000 0.15 X 2 = 0.30 km	0.30	0.60 km
ITEM 622- PORTABLE CONCRETE BARRIER, 813mm	STA. 8+082.284 TO STA. 8+095.611, 15.30 m STA. 8+104.761 TO STA. 8+126.086, 21.35 m	36.65	STA. 8+082.284 TO STA. 8+095.611, 15.30 m STA. 8+104.761 TO STA. 8+110.861, 6.1 m	21.40	58.05 m, USE 58 m
ITEM 622- PORTABLE CONCRETE BARRIER, 813mm, BRIDGE MOUNTED	STA. 8+095.611 TO STA. 8+104.761 (C), 9.15 m	9.15	STA. 8+095.611 TO STA. 8+104.761 (C), 9.15 m	9.15	18.3 m, USE 18 m

\* QUANTITIES CARRIED TO GENERAL SUMMARY

MAINTENANCE OF TRAFFIC QUANTITIES

LAK-528-8.095