



PAVEMENT		301	301	304	310	310	404	409	409	411	452	611	SPE	203	203
REF	LOCATION	5" BITUMINOUS AGGREGATE BASE, AC-20	BITUMINOUS AGGREGATE BASE, AC-20, RT-11 OR 12	AGGREGATE BASE	6" SUBBASE TYPE 2	SUBBASE VARIABLE DEPTH, TYPE 2	1" ASPHALTIC CONCRETE	SEAL COAT BITUMINOUS MATERIAL	SEAL COAT COVER AGGREGATE, NO. 8	8" STABILIZED CRUSHED AGGREGATE	7" PLAIN PORTLAND CEMENT CONCRETE	REINFORCED CONCRETE APPROACH SLAB (7'-12")	PRESSURE RELIEF JOINT, STD. TYPE A	EMBANKMENT	DRIVE EXCAVATION
		CY.	CY.	CY.	CY.	CY.	CY.	GAL.	CY.	CY.	SY.	LF.		CY.	CY.
P-1	40+60.28-44+78.92				186.1						1116.4				
P-2	40+45.28-44+00 L.		15.8	13.1		19.1		63.0	1.3						
P-3	44+67.5-44+78.92 L.		0.6	0.5		0.7		2.1	0.05						
P-4	40+45.28-41+78 R.		5.8	4.9		7.2		23.6	0.5						
P-5	42+07-44+78.92 R.		11.8	10.1		14.6		48.3	1.0						
P-6	DRIVE 41+97 (COMM.) R.									8.1				9.3	8.1
P-7	DRIVE 44+35 (COMM.) L.		18.5				4.0								22.1
P-8	40+45.28-40+60.28											40			
P-9	41+00-41+04											24.37			
TOTALS		19	34	29	187	42	4	137	3	9	1117	40	25	10	31

TRAFFIC CONTROL		621	621	630	630	604
REF	LOCATIONS	4" SINGLE YELLOW DASHED CENTERLINE	4" SOLID WHITE EDGE LINE	SIGN FLAT SHEET	GROUND MOUNTED SUPPORTS No. 3 POSTS	REMOVE & RELOCATE EX. HISTORICAL MARKER
C/L		MI.	MI.	SF.	LF.	EA.
R & L	40+38-44+78.92	0.08				
RT	43+00 (R-10-24)		0.16		5	13
RT	44+30 (HISTORICAL MARKER)					1
TOTALS		0.08	0.16	5	13	1

NOTE: ALL EXISTING TRAFFIC CONTROL SIGNS SHALL BE REMOVED. REMOVED ITEMS SHALL BE STORED ON THE PROJECT FOR SALVAGE BY THE VILLAGE OF FAIRPORT HARBOR. COST OF REMOVAL AND STORAGE SHALL BE INCLUDED IN ITEM 201 CLEARING AND GRUBBING.