

FOR PLAN VIEWS SEE SHEETS 61 THRU 62  
FOR TYPICAL SECTIONS SEE SHEET 3

# SIDEWALK & CURB SUB-SUMMARY

CALC. BY J.J.C. DATE 1/93 CHKD. BY C.C.H. DATE 1/93	LAK - 535 - 0.55	OHIO FHWA REGION 5	77 90
--	------------------	-----------------------	----------

PLANS NO. 271

SIDEWALK SUB-SUMMARY						608	608	608
STREET NAME	STATION TO STATION	SIDE	LENGTH FEET	SUBTRACT FOR DRIVES	LENGTH X WIDTH	4" CONCRETE WALK	CURB RAMP, TYPE 1	CURB RAMP, TYPE 2
						SQ. FT.	EACH	EACH
EAST STREET (S.R. 535)	49+55.14 TO 83+24.00	LT.	3368.86	291.0	3007.86 x 7.0	21545		
	83+60.00 TO 85+90.00	LT.	230.00		230.00 x 7.0	1610	1	
	86+42.50 TO 89+29.50	LT.	287.00	126.5	160.50 x 7.0	1124	2	
	89+75.00 TO 95+37.00	LT.	562.00		562.00 x 7.0	3934	2	
	95+92.00 TO 96+14.36	LT.	22.36		22.36 x 7.0	157	1	
	49+55.00 TO 60+88.00	RT.	1133.00	135.0	998.00 x 7.0	6986		1
	61+70.00 TO 83+74.00	RT.	2204.00	221.0	1983.00 x 7.0	13881		1
	84+10.00 TO 95+20.00	RT.	1110.00	75.0	1035.00 x 7.0	7245		1
95+92.00 TO 96+14.36	RT.	22.36		22.36 x 7.0	157			
NEW STREET	9+57.97 TO 9+78.00	LT. & RT.	20.23		20.23 x 10.0	200		
SEVENTH STREET	9+60.70 TO 9+80.00	LT. & RT.	19.30		19.30 x 10.0	193		
SIXTH STREET	9+60.29 TO 9+79.00	LT. & RT.	18.71		18.71 x 10.0	187		
TOTAL						57,219	6	3

FOR PLAN VIEWS SEE SHEETS 9 THRU 21  
FOR TYPICAL SECTIONS SEE SHEET 3

CURB				609	609
STREET NAME	STATION TO STATION	SIDE		CURB, TYPE 6	CURB, TYPE 2-B
				LIN. FT.	LIN. FT.
EAST STREET (S.R. 535)	STA. 49+55.14 TO STA. 83+30.00	LT.		3375	
	STA. 83+60.60 TO STA. 85+76.52	LT.			216
	STA. 85+76.52 TO STA. 9+57.97	LT.			43
	STA. 9+57.97 TO STA. 86+56.30	LT.			41
	STA. 86+56.30 TO STA. 89+16.63	LT.			261
	STA. 89+16.63 TO STA. 9+60.70	LT.			42
	STA. 9+60.70 TO STA. 89+88.72	LT.			40
	STA. 89+88.72 TO STA. 95+25.07	LT.			537
	STA. 95+25.07 TO STA. 9+60.29	LT.			40
	STA. 9+60.89 TO STA. 96+04.12	LT.			40
	STA. 96+04.12 TO STA. 96+14.36	LT.			10
	STA. 47+60.00 TO STA. 60+71.06	RT.			1311
	STA. 60+71.06 TO STA. 10+71.32	RT.			78
	STA. 10+66.36 TO STA. 61+88.74	RT.			82
	STA. 61+88.74 TO STA. 83+70.00	RT.			2182
	STA. 84+03.00 TO STA. 95+00.47	RT.			1098
	STA. 95+00.47 TO STA. 10+64.15	RT.			79
	STA. 10+64.15 TO STA. 96+04.34	RT.			64
STA. 96+04.34 TO STA. 96+14.36	RT.			10	
TOTAL				7028	2521

SIDEWALK & CURB SUB-SUMMARY TOTALS  
CARRIED TO GENERAL SUMMARY

90483 MON 02/01/93 08:50:47 AM JACK FILES: WALKSUM.PLT