WATERWORKS SUB-SUMMARY

CALC. BY J.J.C. DATE 1/93	LAK - 535 - 0.55	OHIO
CHKD. BY C.C.H. DATE 1/93		FHWA REGION 5

87/90

PLAN NO. 271

DRAINAGE		638	638	638	638	638	638	638	638	638	604
SHEET NO.	STREET NAME	VALVE BOX ADJUSTED TO GRADE	SERVICE BOX ADJUSTED TO GRADE	FIRE HYDRANT ADJUSTED TO GRADE	FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE	FIRE HYDRANT & GATE VALVE REMOVED AND RESET, AS PER PLAN	6" WATER MAIN D. I. P. CL. 52 MECHANICAL JOINTS AND FITTINGS	6" GATE VALVE AND VALVE BOX	4" CUTTING-IN SLEEVE, VALVE & VALVE BOX	10" CUTTING-IN SLEEVE, VALVE & VALVE BOX	MANHOLE ADJUSTED TO GRADE, AS PER PLAN
		EACH	EACH	EACH	EACH	EACH	L. F.	EACH	EACH	EACH	EACH
9	S. R. 535 STA. 47+60 TO STA. 51+00										
10	S. R. 535 STA. 51+00 TO STA. 55+00	1									
11	S. R. 535 STA. 55+00 TO STA. 59+00					1					
12	S. R. 535 STA. 59+00 TO STA. 63+00	1		1							
13	S. R. 535 STA. 63+00 TO STA. 67+00			1							
14	S. R. 535 STA. 67+00 TO STA. 71+00										
15	S. R. 535 STA. 71+00 TO STA. 75+00										
16	S. R. 535 STA. 75+00 TO STA. 79+00	1	1		1						
17	S. R. 535 STA. 79+00 TO STA. 83+00										
18	S. R. 535 STA. 83+00 TO STA. 87+00	3					82	1		1	
19	S. R. 535 STA. 87+00 TO STA. 91+00										
20	S. R. 535 STA. 91+00 TO STA. 95+00	1			1						1
21	S. R. 535 STA. 95+00 TO STA. 98+00								1		
22	EASEMENT STA. 0+00 TO STA. 3+00										
23	EASEMENT STA. 3+00 TO STA. 4+80										
DRAINAGE SUB-SUMMARY TOTALS		7	1	2	2	1	82	1	1	1	1
TOTALS CARRIED TO GENERAL SUMMARY											

90483 THU 01/28/93 04:45 PM JACK FILES: WATERSUM.PLT