

GENERAL SUMMARY

PLAN NO 271

ITEM	SHEET NUMBERS																	
	4	5	7	75	76	77	78	81	82	83	84	85	86	87				
202							713			846								
202										5076								
202										2272								
202										315								
202										10								
203	40				1624		104				2642							
203											4167							
254					11351													
254	770																	
608						58549												
608						6												
608						3												
207	400																	
207	544																	
659											5689							
659										0.75								
659										3.73								
660											2591							
251	1550																	
252	80					475												
252	700					494												
252	1600					2110												
301					770		119											
304					770		58											
305					1104													
310	40																	
402					747													
404					534													
404							24											
407					1154													
452							177											
452							627											
452					43													
609							2521											
609							7028											

ITEM	ITEM EXT.	QUANT.	UNIT	DESCRIPTION	AS PER PLAN DESG.
ROADWAY					
202	23000	1559	SQ. YD.	PAVEMENT REMOVED	
202	30000	5076	SQ. FT.	WALK REMOVED	
202	32000	2272	LIN. FT.	CURB REMOVED	
202	35100	315	LIN. FT.	PIPE REMOVED, 24" & UNDER	
202	58500	10	EACH	CATCH BASIN ABANDONED	
203	12000	4410	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
203	20000	4167	CU. YD.	EMBANKMENT	
254	01000	11351	SQ. YD.	PAVEMENT PLANING, BITUMINOUS, 3" DEPTH	
254	01600	770	SQ. YD.	PATCHING PLANED SURFACE	
608	10000	58549	SQ. FT.	4" CONCRETE WALK	
608	50000	6	EACH	CURB RAMP, TYPE 1	
608	51000	3	EACH	CURB RAMP, TYPE 2	
EROSION CONTROL					
207	30000	400	LIN. FT.	FILTER FABRIC FENCE	
207	70000	544	EACH	STRAW OR HAY BALES	
659	10000	5689	SQ. YD.	SEEDING AND MULCHING	
659	20000	0.75	TON	COMMERCIAL FERTILIZER	
659	30000	3.73	TON	AGRICULTURAL LIMING	
660	30001	2591	SQ. YD.	SODDING, AS PER PLAN	4
PAVEMENT					
251	01000	1550	SQ. YD.	PARTIAL DEPTH PAVEMENT REPAIR	
252	01000	555	SQ. YD.	FULL DEPTH RIGID PAVEMENT REMOVAL AND FLEXIBLE REPLACEMENT, TYPE I	
252	01000	1194	SQ. YD.	FULL DEPTH RIGID PAVEMENT REMOVAL AND FLEXIBLE REPLACEMENT, TYPE II	
252	01500	3710	LIN. FT.	FULL DEPTH PAVEMENT SAWING	
301	10002	889	CU. YD.	BITUMINOUS AGGREGATE BASE, AC-20	
304	20001	828	CU. YD.	AGGREGATE BASE, AS PER PLAN	4
305	13001	1104	SQ. YD.	9" CONCRETE BASE, AS PER PLAN	4
310	12001	40	CU. YD.	SUBBASE, TYPE 1, GRADING A, AS PER PLAN	4
402	20000	747	CU. YD.	ASPHALT CONCRETE, AC-20	
404	20000	534	CU. YD.	ASPHALT CONCRETE, AC-20	
404	25000	24	CU. YD.	ASPHALT CONCRETE, AC-20 (DRIVEWAYS)	
407	10000	1154	GAL.	TACK COAT	
452	10000	177	SQ. YD.	6" PLAIN CONCRETE PAVEMENT	
452	12000	627	SQ. YD.	8" PLAIN CONCRETE PAVEMENT	
452	13000	43	SQ. YD.	9" PLAIN CONCRETE PAVEMENT	
609	16000	2521	LIN. FT.	CURB, TYPE 2-B	
609	26000	7028	LIN. FT.	CURB, TYPE 6	