GENERAL SUMMARY

CALC. BY	J.J.C.
DATE	1/93
CHKD. BY	C.C.H.
DATE	1/93

LAK - 535 - 0.55

OHIO

FHWA REGION 5

90/90

PLAN NO. 271

ITEM	SHEET NUMBERS 4	5		7			75	76	77	78			81	82	83	84	85	86	87						
638																			82						
638																			1						
638																			1						
638																			1						
638																			2						
638																			2						
638																			1						
638																			7						
638				10															1						
SPECIAL				200																					
SPECIAL				4																					
SPECIAL				4																					
404		100																							
410		100																							
614		1.00																							
616	60	20																							
616	6	2																							
642																		0.86							
642																		100							
642																		518							
642																		236							
614																									
619																									
623																									
624																									

ITEM	ITEM EXT.	QUANT.	UNIT	DESCRIPTION	AS PER PLAN DESG.
				WATERWORKS	
638	00700	82	LIN. FT.	6" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 52 MECHANICAL JOINTS AND FITTINGS	
638	07800	1	EACH	6" GATE VALVE AND VALVE BOX	
638	08800	1	EACH	4" CUTTING-IN SLEEVE, VALVE AND VALVE BOX	
638	09100	1	EACH	10" CUTTING-IN SLEEVE, VALVE AND VALVE BOX	
638	10300	2	EACH	FIRE HYDRANT EXTENDED AND ADJUSTED TO GRADE	
638	10400	2	EACH	FIRE HYDRANT ADJUSTED TO GRADE	
638	10601	1	EACH	FIRE HYDRANT AND GATE VALVE REMOVED AND RESET, AS PER PLAN	74
638	10800	7	EACH	VALVE BOX ADJUSTED TO GRADE	
638	10900	11	EACH	SERVICE BOX ADJUSTED TO GRADE	
SPECIAL	638 44006	200	LB.	MISCELLANEOUS METAL WORK	
SPECIAL	638 45000	4	EACH	3/4" WATER SERVICE CONNECTION, LONG SIDE	
SPECIAL	638 45400	4	EACH	3/4" WATER SERVICE CONNECTION, SHORT SIDE	
				MAINTENANCE OF TRAFFIC	
404	35000	100	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
410	12000	100	CU. YD.	TRAFFIC COMPACTED SURFACE, TYPE A OR B	
614	21400	1.00	MILE	TEMPORARY CENTERLINE, CLASS II, 642 PAINT	
616	10000	80	M GAL.	WATER	
616	20000	8	TON	CALCIUM CHLORIDE	
				PAVEMENT MARKING	
642	00302	0.86	MILE	DOUBLE YELLOW CENTERLINE, TYPE 2	
642	00502	100	LIN. FT.	STOPLINE, TYPE 2	
642	00602	518	LIN. FT.	CROSSWALK LINE, TYPE 2	
642	01002	2	EACH	RAILROAD SYMBOL MARKING, TYPE 2	
614	11000	LUMP	LUMP	MAINTAINING TRAFFIC	
619	10000	LUMP	LUMP	FIELD OFFICE, TYPE A	
623	10000	LUMP	LUMP	CONSTRUCTION LAYOUT STAKES	
624	10000	LUMP	LUMP	MOBILIZATION	

90483 THU 01/28/93 04:45 PM JACK FILES: GS3.PLT