

LAKE COUNTY  
LAK-615-3.26

QUANTITIES FOR DETOUR ROUTE					
LOCATION	402	404	407	411	604
	Asphalt Concrete	Asphalt Concrete	Tack Coat	Stabilized crushed Aggregate	Manhole Adjusted to Grade
	C.Y.	C.Y.	Gal.	C.Y.	EA.
Acacia Avenue	157	104	375	148	8
Hart Street	30	20	70	28	
Station Street	52	34	123	38	
TOTAL	239	158	568	214	8

SHEET NO.	Subgrade Compaction	Concrete Walk	Concrete Steps
	ITEM 203	ITEM 608	ITEM 608
	S.Y.	S.F.	L.F.
56	2921	3386	
57	4804	4959	116
58	3520	4688	
59	2882	2905	
60	3400	5011	
61	2879	<del>2911</del> 592*	
62	3258	5134*	
63	4202	5431*	
64	2144	3725*	
65	764	60*	
66	3309	5662*	
67	4063	4610*	
68	4068	4673*	
69	3500	4505*	
70	2971	3213*	
71	3723	4183*	
72	3839	5019*	
73	3160		
74	578		
TOTAL NORMAL	59,985	23,860	116
TOTAL 100% CITY	—	46,807	—
GRAND TOTAL	59,985	70,667	116

\* 100% City Participation

EARTHWORK AND SEEDING QUANTITIES				
LOCATION	203		659	
	EXCAVATION	EMBANKMENT	SEEDING AND MULCHING	
	C.Y.		S.Y.	
SR 615				
2+42.00	8+00.00	1801	0	786
8+00.00	16+00.00	4000	0	1002
16+00.00	23+00.00	3508	0	1384
23+00.00	30+00.00	2922	0	1477
30+00.00	37+50.00	3895	56	2067
37+50.00	45+00.00	1222	18,428	4470
45+00.00	52+00.00	1025	24425	5306
52+00.00	59+00.00	482	60855	9972
59+00.00	66+00.00	1232	14271	4656
66+00.00	73+00.00	4955	38	1555
73+00.00	79+81.00	4850	644	2897
MENTOR AVE.				
3+00.00	9+50.00	2370	9	1034
10+50.00	17+51.00	2582	25	936
PROSPECT ST.		571	0	523
NOWLEN ST.		498	0	546
SERVICE RD. B		3	335	728
STATION ST.		430	0	359
SERVICE RD. D		3805	0	2310
TYLER BLVD.		715	0	227
KELLY DR.		59	6	110
RETENTION BASIN		111,903	0	37991
TOTAL		180,246	119,336	79,745

ITEM 659 COMMERCIAL FERTILIZER

Seeding and Mulching 79,745 S.Y.  
Sodding 535 S.Y.  
80,290 S.Y.

$0.00009 \times 80,290 \text{ S.Y.} = 723 \text{ Tons}$

ITEM 659 AGRICULTURAL LIMING

$0.00045 \times 80,290 \text{ S.Y.} = 36.13 \text{ Tons}$

QUANTITY CALCULATIONS  
BY SR DATE 4-6-69  
CHKD. EDT DATE 4-6-69  
BURGESS & NIPLÉ, LIMITED

SUB-SUMMARY