

CALC. BY JJK
DATE 10/90
CHKD. BY BJW
DATE 1-91

LAK - 615 - 5.12

OHIO

FHWA REGION

16
164

PAVEMENT SUB-SUMMARY

LOCATION	STATION TO STATION	SIDE	ACTUAL LENGTH (FT.)	SUBTRACT FOR DRIVES	LENGTH X AVE. WIDTH	404	301	304	203	SPECIAL
						C.Y.	C.Y.	C.Y.	S.Y.	S.Y.
CENTER STREET	STA. 10+63 TO STA. 19+19	RT.	856		856 X 10	39.6	79.3		951.1	951.1
	STA. 19+19 TO STA. 19+37	RT.	8		8 X 5	0.2	0.4		4.5	4.5
	STA. 19+79 TO STA. 19+89	RT.	10		10 X 5	0.3	0.5		5.6	5.6
	STA. 19+89 TO STA. 27+55	RT.	766		766 X 10	35.5	71.0		851.1	851.1
	STA. 27+55 TO STA. 27+75	RT.	20		20 X 14.3	1.4	2.7		31.8	31.8
	STA. 125+53 TO STA. 125+63	RT.	10		10 X 5	0.3	0.5		5.6	5.6
	STA. 125+63 TO STA. 129+61	RT.	398	55	343 X 10	15.9	31.8		381.1	381.1
	STA. 130+03 TO STA. 130+16	RT.	13		13 X 5	0.3	0.6		7.2	7.2
	STA. 130+16 TO STA. 131+17	RT.	101		101 X 10	4.7	9.4		112.2	112.2
	STA. 131+17 TO STA. 131+31	RT.	14		14	0.4	0.7		7.8	7.8
CENTER STREET EXTENSION	STA. 131+86 TO STA. 132+00	RT.	14		14 X 5	0.4	0.7		7.8	7.8
	STA. 132+00 TO STA. 133+46.52	RT.	146.52		146.52 X 10	6.8	13.6		162.8	162.8
	STA. 133+46.52 TO STA. 138+36.95	RT.	497.87	22	475.87 X 10	22.0	44.1		528.7	528.7
	STA. 138+36.95 TO STA. 143+30.87	RT.	494.64	25	469.64 X 10	21.7	43.5		521.8	521.8
	STA. 143+30.87 TO STA. 148+19.82	RT.	483.83	29	454.83 X 10	21.1	42.1		505.4	505.4
	STA. 148+19.82 TO STA. 149+78	RT.	158.90		158.90 X 10	7.4	14.7		176.6	176.6
HENDRICKS ROAD	STA. 149+78 TO STA. 149+86	RT.	8		8 X 5	0.2	0.4		4.5	4.5
	STA. 10+29 TO STA. 10+56	LT.	34.6		34.6 X 10	1.6	3.2		38.5	38.5
	STA. 10+56 TO STA. 24+11.36	LT.	1355.36		1355.36 X 10	62.8	125.5		1506.0	1506.0
	STA. 24+11.36 TO STA. 25+90.86	LT.	176.60		176.60 X 10	8.2	16.4		196.2	196.2
	STA. 25+90.86 TO STA. 26+12	LT.	24		24 X 10	1.1	2.2		26.7	26.7
HOPKINS ROAD	STA. 26+12 TO STA. 26+15	LT.	14.6		14.6 X 5	0.4	0.7		8.1	8.1
	STA. 50+40 TO STA. 50+56	LT.	13		13 X 13.6	0.9	1.7		19.7	19.7
	STA. 50+56 TO STA. 54+04	LT.	352		352 X 10	16.3	32.6		391.1	391.1
	STA. 54+04 TO STA. 54+28	LT.	24.7		24.7 X 10	1.2	2.3		27.5	27.5
	STA. 54+28 TO STA. 64+18	LT.	956		956 X 10	44.3	88.6		1062.2	1062.2
	STA. 64+18 TO STA. 64+44	LT.	26		26 X 5	0.6	1.2		14.5	14.5
TRAIL ROUTE	STA. 0+02 TO STA. 0+24	C	16		16 X 13.7	1.0	2.1		24.4	24.4
	STA. 0+24 TO STA. 3+00	C	276		276 X 12	15.4	30.7		368.0	368.0
	STA. 3+00 TO STA. 3+50	C	50		50 X 11	2.6	5.1		61.1	61.1
	STA. 3+50 TO STA. 6+74	C	324		324 X 10	15.0	30.0		360.0	360.0
	STA. 6+74 TO STA. 6+77	C	3		3 X 5	0.1	0.2		1.7	1.7
SUB-TOTALS						349.7	698.5		8371.3	8371.3

LOCATION	STATION TO STATION	SIDE	ACTUAL LENGTH (FT.)	SUBTRACT FOR DRIVES	LENGTH X AVE. WIDTH	404	301	304	203	SPECIAL
						C.Y.	C.Y.	C.Y.	S.Y.	S.Y.
HOPKINS ROAD	STA. 81+13 TO STA. 81+21	LT.	10		10 X 5	0.3	0.5		5.6	5.6
	STA. 81+21 TO STA. 89+00	LT.	776		776 X 10	35.9	71.9		862.3	862.3
	STA. 89+00 TO STA. 90+00	LT.	100		100 X 11	5.1	10.2		122.3	122.3
	STA. 90+00 TO STA. 93+50	LT.	350		350 X 12	19.5	38.9		466.7	466.7
	STA. 93+50 TO STA. 94+50	LT.	100		100 X 11	5.1	10.2		122.3	122.3
	STA. 94+50 TO STA. 95+09	LT.	59		59 X 10	2.8	5.5		65.6	65.6
	STA. 95+09 TO STA. 95+18	LT.	8		8 X 5	0.2	0.4		4.5	4.5
	STA. 95+45 TO STA. 95+54	LT.	9		9 X 5	0.2	0.4		5.0	5.0
	STA. 95+54 TO STA. 99+72	LT.	469		469 X 10	21.7	43.5		521.1	521.1
	STA. 99+72 TO STA. 99+90	LT.	18		18 X 5	0.5	0.9		10.0	10.0
	STA. 100+52 TO STA. 100+58	LT.	5		5 X 2.5	0.1	0.2	0.3	1.4	1.4
	STA. 100+58 TO STA. 130+61 (EXT.)	LT.	3106	116	2990 X 5	68.8	139.1	276.6	1661.1	1661.1
	STA. 100+35 TO STA. 100+46	RT.	10		10 X 2.5	0.2	0.3	0.5	2.8	2.8
	STA. 100+46 TO STA. 126+35	RT.	2600		2600 X 5	60.2	120.4	240.7	1444.4	1444.4
	STA. 127+00 TO STA. 130+48	RT.	349		349 X 5	8.1	16.2	32.3	193.9	193.9
	STA. 130+79 TO STA. 131+00	LT.	21		21 X 5	0.5	1.0		11.7	11.7
	STA. 131+00 TO STA. 132+50	LT.	150		150 X 10	7.0	13.9		166.7	166.7
	STA. 132+50 TO STA. 132+54	LT.	4		4 X 5	0.1	0.2		2.2	2.2
	STA. 132+65 TO STA. 132+69	LT.	4		4 X 5	0.1	0.2		2.2	2.2
	STA. 132+69 TO STA. 133+50	LT.	81		81 X 10	3.8	7.5		90.0	90.0
	STA. 133+50 TO STA. 133+57	LT.	7		7 X 5	0.2	0.4		3.9	3.9
	STA. 133+71 TO STA. 133+77	LT.	6		6 X 5	0.2	0.3		3.4	3.4
	STA. 133+77 TO STA. 147+48	LT.	1371		1371 X 5	63.5	127.0		1523.4	1523.4
	STA. 147+48 TO STA. 147+61	LT.	13		13 X 5	0.3	0.6		7.2	7.2
	STA. 147+03 TO STA. 148+01	LT.	8		8 X 5	0.2	0.4		4.4	4.4
	STA. 148+01 TO STA. 149+34	LT.	133		133 X 10	6.2	12.3		147.8	147.8
	STA. 149+34 TO STA. 149+50	LT.	16		16 X 5	0.4	0.8		8.9	8.9
	STA. 150+03 TO STA. 150+18	LT.	15		15 X 5	0.4	0.7		8.3	8.3
STA. 150+18 TO STA. 154+13	LT.	395		395 X 10	18.3	36.6		438.9	438.9	
STA. 154+13 TO STA. 154+21	LT.	8		8 X 5	0.2	0.4		4.4	4.4	
SUB-TOTALS						330.1	660.9	550.4	7912.4	4608.8
SHEET TOTALS						680	1360	551	16,284	12,980