GENERAL SUMMARY

CALC. BY JJC DATE 12-90	LAK – 615 – 5.12	OHIO
CHKD. BY DJW DATE 1-91		FHWA REGION 5

ITEM	SHEET NUMBER 13	14	16	17	18	ITEM	ITEM EXT.	QUANTITY	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION
										ROADWAY	
201	LUMP					201	11000	LUMP		CLEARING AND GRUBBING	
202				LUMP		202	11000	LUMP		STRUCTURE REMOVED	
202				241		202	23000	241	SQ. YD.	PAVEMENT REMOVED	
202				1750		202	30000	1750	SQ. FT.	WALK REMOVED	
202				263		202	32000	263	LIN. FT.	CURB REMOVED	
202				263		202	35100	263	LIN. FT.	PIPE REMOVED, 24" AND UNDER	
202				856		202	38000	856	LIN. FT.	GUARDRAIL REMOVED	
202				4		202	58100	4	EACH	CATCH BASIN REMOVED	
202				7		202	98100	7	EACH	REMOVAL MISCELLANEOUS: GUARD POST	
203				4398		203	12000	4398	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
203				4053		203	20000	4053	CU. YD.	EMBANKMENT	
203			16284			203	50000	16284	SQ. YD.	SUBGRADE COMPACTION	
517				126		517	73501	126	LIN. FT.	RAILING, PIPE, AS PER PLAN	13
606				37.5		606	13000	37.5	LIN. FT.	GUARDRAIL, TYPE 5	
606				825		606	13001	825	LIN. FT.	GUARDRAIL, TYPE 5, AS PER PLAN	145
606				1		606	17901	1	EACH	GUARD POST, AS PER PLAN	13
606				5		606	25001	5	EACH	ANCHOR ASSEMBLY, TYPE A, AS PER PLAN	145
606				2		606	26501	2	EACH	ANCHOR ASSEMBLY, TYPE T, AS PER PLAN	145
606				4		606	35141	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4, AS PER PLAN	145
616	50					616	10000	50	M-GAL.	WATER	
										EROSION CONTROL	
207		4265				207	10000	4265	SQ. YD.	TEMPORARY SEEDING AND MULCHING	
207		1000				207	30000	1000	LIN. FT.	FILTER FABRIC FENCE	
207		500				207	50000	500	CU. YD.	TEMPORARY BENCHES, DAMS AND SEDIMENT BASINS	
207		1000				207	70000	1000	EACH	STRAW OR HAY BALES	
601				2		601	32200	2	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
659				21323		659	10000	21323	SQ. YD.	SEEDING AND MULCHING	
659		1067				659	14000	1067	SQ. YD.	REPAIR SEEDING AND MULCHING	
659		1			2	659	20000	3	TON	COMMERCIAL FERTILIZER	
659					9.6	659	30000	10	TON	AGRICULTURAL LIMING	
659		10			47	659	35000	57	M-GAL.	WATER	
670				584		670	40000	584	SQ. YD.	DITCH EROSION PROTECTION	