SIGNING SUB SUMMARY

STATION	LOCATION	OFFSET	R. OR L.	ITEM 630 – SIGNS, FLAT SHEET R-1-18	W-7-24	W-13A-24	W-14A-24	W-65-18	W-76B-30	R-147	R-151	R5-3-24*	M7-4-12*	M7-6-12*	M7-4A-12*	M7-6A-12*	SPECIAL-24	ITEM 630 GROUND MOUNTED SUPPORTS No. OF POST REQ'D	No.3	No.4	ITEM 630 REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	REMOVAL OF GROUND MOUNTED SIGN AND RE-ERECTION	REMOVAL OF GROUND MOUNTED POST SUPPORT & DISPOSAL
				SQUARE FEET														EACH	LINEAR FEET		EACH	EACH	EACH
81+20	HOPKINS ROAD	40	L	2.25														1	14				
81+50		35	L									4.0						1	14				
82+00		35	L		3.0													1	14				
84+28		38	L															1	14			1	1
89+00		35	L					2.25										1	14				
94+50		30	L					2.25										1	14				
95+14		29	L															1	14			1	1
96+84		23	L															1	14			1	1
97+50		17	R						6.25									1	14				
99+00		35	L		3.0													1	14				
99+00		18	R							5.0								1	14				
99+50		35	L									4.0						1	14				
99+50		18	R		3.0												3.0	1	14				
101+00		23	L							5.0								1	14				
101+00		20	R								5.0	4.0						1		17			
101+50		25	L		3.0									.75				1	14				
103+25		25	L						6.25									1	14				
111+50		23	R					2.25										1	14				
123+50		26	L					2.25										1	14				
126+92		44	R															1	14			1	1
127+50		20	R						6.25									1	14				
129+50		20	R		3.0								.75					1	14				
130+00		26	L									4.0						1	14				
130+00		25	R							5.0	5.0							2	17				
130+28		30	R															1	14			1	1
131+05		30	L															1	14			1	1
131+75		30	L									4.0			.75			1	15				
131+75		30	L							5.0								1	15				
132+25		30	L		3.0													1	14				
133+00		32	L						6.25									1	14				
153+00		30	L		3.0		1.0											1	14				
154+00		30	L		3.0	1.0						4.0						1		14			
				2.25	24.0	1.0	1.0	9.0	25.0	20.0	10.0	24.0	.75	.75	.75		3.0						
TOTALS				121.50														33	425	31		6	6

* FEDERAL MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES