

SHEET NO.	SECTION NO.	PHASE NO.	STATION		603	614	614	614	614	614		614	614		614	614	614	614	615	622				
					300 mm CONDUIT, TYPE B, AS PER PLAN, 706.02	TEMPORARY LANE LINE, CLASS 1 642 PAINT	TEMPORARY SOLID DOUBLE CENTER LINE CLASS 1, 642 PAINT	TEMPORARY SOLID DOUBLE CENTER LINE CLASS 1, 740.06 TYPE 1	TEMPORARY YELLOW EDGE LINE CLASS 1, 642 PAINT	TEMPORARY WHITE EDGE LINE CLASS 1, 642 PAINT		TEMPORARY YELLOW EDGE LINE, CLASS 1 740.06, TYPE 1	TEMPORARY WHITE EDGE LINE 740.06, TYPE 1		TEMPORARY CHANNELING LINE CLASS 1, 740.06 TYPE 1	TEMPORARY DOTTED LINE CLASS 1, 740.06 TYPE 1	TEMPORARY STOP LINE CLASS 1, 642 PAINT	TEMPORARY STOP LINE, CLASS 1 740.06, TYPE 1	TEMPORARY CROSSWALK LINES CLASS 1, 740.06 TYPE 1	TEMPORARY PAVEMENT CLASS A	PORTABLE CONCRETE BARRIER, 813 mm			
					METERS	METERS	METERS	METERS	METERS	METERS		METERS	METERS		METERS	METERS	METERS	METERS	METERS	SQ. METER	METERS			
37	1	1	4+100	4+300			37.0					48.0	41.0		35.0	75.0		11.5	90.0	178.0				
38		1	4+300	4+500			200.0																	
38		1	4+500	4+700			200.0																	
39		1	4+700	4+900			143.0	23.0		63.0			24.0			34.0	8.5			36.5				
39		1	4+900	5+100				37.0					8.0											
40	1	2	4+100	4+300				20.0				88.0							11.0					
41		2	4+300	4+500				200.0					20.0											
41		2	4+500	4+700				200.0					163.5											
42		2	4+700	4+900				166.0					118.0			4.2	8.1							
42		2	4+900	5+100				7.0					97.0											
43	2	1	3+250	3+700			161.0	40.0					97.0						32.5					
43		1	3+700	3+900			200.0		43.0	161.0							5.5	7.0		196.0				
44		1	3+900	4+100		35.0	166.0			85.0							8.8							
44		1	4+100	4+300			128.0			136.0		125.0	45.0				16.5			40.5				
45	2	2	3+250	3+700				220.0					196.0				8.0							
45		2	3+700	3+900				200.0					200.0				5.0			75.0				
46		2	3+900	4+100				166.0		40.0			240.0				11.5	15.5		205.0				
46		2	4+100	4+300				142.0					270.0			24.0	4.5	11.5						
47	3	1	4+700	4+900			23.0	31.0		23.0			46.5		35.0					18.0	23.0			
47		1	4+900	5+100			200.0			200.0							6.6			301.0	130.0			
48		1	5+100	5+300			200.0			90.0										307.0	244.0			
48		1	5+300	5+530			63.0					50.0	134.0			130.0	4.0				245.0			
49	3	2	4+700	4+900				70.0					53.0											
49		2	4+900	5+100				200.0					200.0					6.6						
50		2	5+100	5+300				200.0					200.0					6.6						
50		2	5+300	5+530				61.0					83.0		75.0	93.0		7.5						
51	2	RAMP 9 & RAMP 10				47.0				60.0		73.7	70.5					14.0		245.0	101.0			
51A	2	RAMP 11 & RAMP 12				18.0				64.0	20.0	63.0	57.0				15.5			359.0	75.0			
51B	2, 1	BEN-HUR RD. & SKIFF ST.						101.0	13.0	153.0			70.5				10.5	12.2		203.0				
		ESTIMATED QUANTITIES TO BE USED AS DIRECTED BY THE ENGINEER						100.0	250.0	20.0	50.0		50.0	100.0		50.0		10.0	50.0	250.0	50.0			
		TOTALS						35.0	1,821.0	2,334.0	200.0	1,072.0		497.7	2,534.0		145.0	406.0	109.1	121.5	249.5	2,337.0	868.0	
		SUBTOTALS									1,272.0				3,031.7									
		TOTALS CARRIED TO GENERAL SUMMARY				65.0 M	0.04 KM	1.82 KM	2.33 KM		1.27 KM			3.03 KM		145.0 M	406.0 M	109.1 M	121.5 M	249.5 M	2,337.0 SQ M	868.0 M		

TEMPORARY PAVEMENT MARKING SUB-SUMMARY

LAK-640-3.444