* 707.41 NON-PERFORATED, ASTM D-3034 SDR35, 707.33 OR 707.42

REFERENCE NO.	PLAN & PROFILE SHEET NO.	STATION FROM	STATION TO	SIDE	STORM 202: PIPE REMOVED 600 mm AND UNDER (METER)	STORM 202: PIPE REMOVED OVER 600 mm (METER)	STORM 202: MANHOLE REMOVED (EACH)	STORM 202: CATCH BASIN REMOVED (EACH)	STORM 202: INLET BASIN REMOVED (EACH)	STORM 603: 150 mm CONDUIT, TYPE F (*) (METER)	STORM 603: 300 mm CONDUIT, TYPE B, AS PER PLAN (METER)	STORM 603: 300 mm CONDUIT, TYPE C, AS PER PLAN (METER)	STORM 603: 675 mm CONDUIT, TYPE B, AS PER PLAN (62.5 D-LOAD) (METER)	STORM 603: 900 mm CONDUIT, TYPE C, AS PER PLAN (62.5 D-LOAD) (METER)	STORM 603: 900 mm CONDUIT, TYPE C, AS PER PLAN (75 D-LOAD) (METER)	STORM 603: 490 mm X 770 mm CONDUIT, TYPE B, 706.04 H.E. III AS PER PLAN (METER)	STORM 604: CATCH BASIN NO. 3A AS PER PLAN (EACH)	STORM 604: CATCH BASIN NO. 2-2B AS PER PLAN (EACH)	STORM 604: MANHOLE NO. 3 AS PER PLAN (EACH)	STORM 604: MANHOLE RECONSTRUCTED TO GRADE (EACH)	STORM 605: 150 mm SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP (METER)	SANITARY 603: 375 mm CONDUIT, TYPE B AS PER PLAN (METER)	SANITARY 604: MANHOLE NO. 3 AS PER PLAN (EACH)
D1	80	4+300	4+320	R										20					1				
D2		4+300	4+320	R							20	6.9					1						
D3		4+320	4+325	L&R							21.5						1						
D4		4+352		R																1			
D5		4+320	4+380	R								7.1			60		1						
D6		4+380		L&R							27.3						1						
D7		4+380	4+400	R										20					1				
S1		4+353.6		℄																1			
R1		4+328.15		L&R	20.8				1														
R2		4+328.15	4+352	R	26				1														
R3		4+389.2		L&R	20.7				1														
R4		4+389.2	4+400	R	11.0				1														
U1-U6		4+300	4+400	L&R						12											182		
D1	81	4+400	4+438.5	R										38.5									
D2		4+443		R																1			
D3		4+443	4+500	R									14.5			43.5			1				
D4		4+456.5	4+460	R							3.9						1						
D5		4+456.5	4+460	L&R							18						1						
D6		4+438.5	4+488.5	R								50						1					
S1		4+441.5		℄																1			
S2		4+445.6		L																1			
S3		4+455.3		L																1			
S4		4+483.5		L																1			
S5		4+445.6	4+500	L&R																		57.2	1
R1		4+400	4+443	R	49																		
R2		4+447.05		R			1																
R3		4+450	4+456.3	L&R	19				1														
R4		4+450	4+456.3	R	6.5				1														
R5		4+453.3	4+500	R	46.5		1																
R6		4+488.3		R	5.5			1															
U1-U4		4+400	4+500	L&R						6											191		
TOTALS CARRIED TO SHEET 58A					205		2	1	6	18	90.7	64	14.5	78.5	60	43.5	6	1	3	7	373	57.2	1

CALCULATED

CHECKED

ESTIMATED QUANTITIES - STA. 4+300 TO 4+500

LAK-640-3.444

82/214

94014-PG-082-MSG\11-24-00

94-014