

ITEM	SHEET NUMBER													PARTICIPATION		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN REF. SHEET NO.	
	2	22	24A	56	58	58A	59	61	67	99	192			CITY, STATE & FEDERAL	100% CITY							
ROADWAY																						
202				34,421	9793												202	23001	45805	SQ. METER	PAVEMENT REMOVED, AS PER PLAN	22
202						1141.5											202	35100	1141.5	METER	PIPE REMOVED, 600 mm AND UNDER	
202						11											202	58000	11	EACH	MANHOLE REMOVED	
202						43											202	58100	43	EACH	CATCH BASIN REMOVED	
202						19											202	58200	19	EACH	INLET REMOVED	
202							4										202	58700	4	EACH	MANHOLE ABANDONED	
202	4																202	60010	4	EACH	MONUMENT ASSEMBLY REMOVED	
SPECIAL								97.5									SPECIAL	202M70000	97.5	METER	FILL AND PLUG EXISTING CONDUIT	22
202				382													202	75000	382	METER	FENCE REMOVED	
202				39													202	75101	39	METER	FENCE REMOVED FOR STORAGE, AS PER PLAN	22
EROSION CONTROL																						
203		1800			1022		12692	83		269							203	12000	15866	CU. METER	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
203					43		323	7		8							203	20000	381	CU. METER	EMBANKMENT	
203		1800															203	21000	1800	CU. METER	EMBANKMENT USING GRANULAR MATERIAL	
203		15															203	45000	15	HOUR	PROOF ROLLING	
203				26540	9758												203	50000	36298	SQ. METER	SUBGRADE COMPACTION	
517											181						517	76300	181	METER	RAILING, MISC.: HANDRAIL, 38.1mm STAINLESS STEEL	192
604	4																604	38500	4	EACH	MONUMENT ASSEMBLY	
607				362													607	20500	362	METER	FENCE, TYPE CL (GALVANIZED)	
SPECIAL			537														SPECIAL	690M65002	537	METRIC TON	WORK INVOLVING HAZARDOUS WASTE	24A
SPECIAL			5														SPECIAL	690M65020	5	CU. METER	WORK INVOLVING WATER	24A
SPECIAL			5														SPECIAL	690M65024	5	CU. METER	WORK INVOLVING REGULATED WATER	24A
DRAINAGE																						
601				1250													601	21000	1250	SQ. METER	CONCRETE SLOPE PROTECTION	
601										81							601	32104	81	CU. METER	ROCK CHANNEL PROTECTION, TYPE B WITH FABRIC FILTER	
601										145							601	32204	145	CU. METER	ROCK CHANNEL PROTECTION, TYPE C WITH FABRIC FILTER	
601		50															601	34200	50	CU. METER	ROCK CHANNEL PROTECTION, TYPE C WITHOUT FILTER	
660					641		7079										660	30001	7720	SQ. METER	SODDING, UNSTAKED, AS PER PLAN	22
870		1000							8412	309							870	10000	9721	SQ. METER	SEEDING AND MULCHING	
870		250															870	14000	250	SQ. METER	REPAIR SEEDING AND MULCHING	
870		60					708		245								870	20000	1013	KILOGRAM	COMMERCIAL FERTILIZER	
870		32200															870	35000	32200	CU. METER	WATER	
877		1500															877	10000	1500	SQ. METER	TEMPORARY SEEDING AND MULCHING	
877		2000							1749								877	30100	3749	METER	TEMPORARY PERIMETER FILTER FABRIC FENCE	
877		750							628								877	30300	1606	METER	TEMPORARY INLET PROTECTION FILTER FABRIC FENCE	
877		100															877	55500	100	SQ. METER	TEMPORARY DITCH PROTECTION	
602						6.3											602	20000	6.3	CU. METER	CONCRETE MASONRY	

GENERAL SUMMARY

LAK-640-3.444

52
214