

EXTRA AREA SUB-SUMMARY

SHEET NO.	LOCATION	202	203	203	203	254	255	255	301	304	305	448	448	407	451	608	608	608	830	830	660
		PAVEMENT REMOVED AS PER PLAN	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	EMBANKMENT	SUBGRADE COMPACTION	PAVEMENT PLANNING	FULL DEPTH PAVEMENT SAWING	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT	BITUMINOUS AGGREGATE BASE PG 64-22, AS PER PLAN	150 mm AGGREGATE BASE AS PER PLAN	150 mm CONCRETE BASE	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1 PG 64-22	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22	TACK COAT	230 mm REINFORCED CONCRETE PAVEMENT	100 mm CONCRETE WALK	CURB RAMP TYPE 1	CURB RAMP TYPE 2	CURB TYPE 2A	CURB TYPE 2B	SODDING UNSTAKED AS PER PLAN
		S.M.	C.M.	C.M.	S.M.	S.M.	M.	S.M.	C.M.	C.M.	S.M.	C.M.	C.M.	L.	S.M.	S.M.	EA.	EA.	M.	M.	S.M.
97	MENTOR AVENUE (U.S. RT. 20)						94.0	169.0				7.61	5.41	76.5							
146	RAMP # 9	452.20	41.2	12.6	461.51		4.80			69.23					461.51	20.14		2	56.59		42.8
148	RAMP # 10	475.38	26.9	2.3	473.40		7.28			71.01					473.40	27.30		2	71.34		35.6
150	RAMP # 11	524.01	91.2	6.7	552.93		8.60			82.94					552.93	25.68		2	78.96		64.6
153	RAMP # 12	443.45	15.8	0.3	436.93		6.79			65.54					436.93	28.54		2	53.02		16.5
155	RAMP # 13	763.88	45.1	6.0	794.69		4.90			119.20					794.69	34.51		2	82.58		34.9
157	RAMP # 14	434.10	30.6	0.6	405.96		7.81			60.89					405.96	28.55		2	70.69		29.0
159	RAMP # 15	503.01	42.6	4.8	491.20		8.10			73.68					491.20	26.16		2	71.80		38.9
161	E. 365th. STREET	457.70	40.1		427.67	9.4	9.71			64.15			0.50	4.2	427.67	32.42	2		42.28		15.2
163	LAKELAND BOULEVARD	989.52	106.0		947.35		8.98			142.10					947.35	66.27	2		82.60		36.4
165	MOORELAND AVENUE	399.74	118.9		576.67		5.90		15.29	86.50		4.85	3.45	45.86	474.77	56.27	2		40.40		35.8
167	ST. CLAIR AVENUE	455.88	179.0		687.22	5.45	5.45		14.42	103.08		4.33	3.25	45.71	591.07	32.81	1	1	49.06		102.2
169	BEN HUR ROAD	1019.99	133.0		955.57		12.20			143.34					955.57	37.36		2	98.80		56.0
171	SKIFF STREET	713.79	64.9	1.1	653.14		12.26			97.97					653.14	84.12	2	1	71.46		39.0
173	PATT COURT	237.55	15.87		241.74		0			36.26					241.74	15.10		2	25.44		5.02
174	CHURCH STREET (NORTH)	276.37	14.7	4.8	259.80	7.0	7.0			39.0			0.22	3.15	259.8	11.10		2	41.2		30.5
176	CHURCH STREET (SOUTH)	373.85	26.11	0.8	337.60	6.78	6.78			50.64	168.05	7.56	5.60	78.67	169.55	11.86		2	14.52	46.31	58.6
178	CLARK STREET	528.25	30.2	2.5	432.54		9.81		9.81	64.88	227.75	10.25	7.60	106.90	204.79	90.7	2		15.81	45.68	0
180	ERIE STREET	744.46			621.68		63.71			93.25			19.89	279.76	621.68	107.04	2			68.19	
	STATION 3+539.40						17.4														
TOTAL CARRIED TO GENERAL SUMMARY		9793.13	1022.18	42.50	9757.60	28.63	301.48	169.0	39.52	1463.66	395.8	34.60	45.92	640.75	9163.75	735.83	13	24	966.55	160.18	641.02

EXTRA AREA SUB-SUMMARY

LAK-640-2.14