

REFERENCE NO.	PLAN & PROFILE SHEET NO.	STATION		SIDE	STORM														SANITARY					BENDS AND BRANCHES FOR INFORMATION ONLY	375 mm 30° BEND		
					202				603						604				605	603		604					
					PIPE REMOVED 600 mm AND UNDER	MANHOLE REMOVED	CATCH BASIN REMOVED	INLET BASIN REMOVED	150 mm CONDUIT, TYPE F (*) AS PER PLAN	200 mm CONDUIT TYPE B 707.44 PS 46 MIN., 707.41 NON PERFORATED OR 706.08, AS PER PLAN	300 mm CONDUIT TYPE B, AS PER PLAN	300 mm CONDUIT, TYPE B, 748.01, ANSI CLASS 53 AS PER PLAN	300 mm CONDUIT TYPE C, AS PER PLAN	525 mm CONDUIT TYPE B, AS PER PLAN	365 mm X 575 mm CONDUIT, TYPE B, AS PER PLAN 706.04 H.E. III	490 mm X 770 mm CONDUIT, TYPE B, AS PER PLAN 706.04 H.E. III	CATCH BASIN NO. 3 AS PER PLAN		CATCH BASIN NO. 3A AS PER PLAN	CATCH BASIN NO. 2-2B AS PER PLAN	MANHOLE NO. 3 AS PER PLAN	MANHOLE RECONSTRUCTED TO GRADE	150 mm SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP			300 mm CONDUIT TYPE B, AS PER PLAN	375 mm CONDUIT TYPE B, AS PER PLAN
METER	EACH	EACH	EACH	METER	METER	METER	METER	METER	METER	METER	METER	METER	EACH		EACH	EACH	EACH	EACH	METER	METER	METER	EACH	EACH				
D1	83	4+500	4+540	R							7.8				40												
D2		4+528.5	4+540	L								12.3															
D3		4+539	4+540	R								2.3															
D4		4+540		L&R							17.1																
D5		4+549		R					3	7.5																	
D6		4+540	4+600	R										60													
D7		4+540	4+569.06	L							29.1																
D8		4+569	4+570.09	R							3																
D9		4+569.06	4+600	L							7	31															
S1		4+500	4+525	R																			25	1			
S2		4+525	4+600	R																			75				
S3		4+582.5		L																1							
R1		4+509		L&R	2		1																				
R2		4+509	4+521.5	L	29.5		1	1																			
R3		4+548	4+549.5	L&R	17		1																				
R4		4+548	4+549.5	R	2		1																				
R5		4+500	4+600	R	100	1																					
R6		4+586.5		L&R	17		1																				
R7		4+586.5		R	2.5		1																				
U1-U6		4+500	4+600	L&R					18																178.9		
D1	84	4+600	4+602.17	L							2.2				1												
D2		4+607.8	4+609	R							2.4				1												
D3		4+600	4+619.25	R							2.4			19.3													
D4		4+649.5	4+665	R							17.4		11.4					1		1							
D5		4+619.25	4+665	R							5.5			45.8				1		1							
D6		4+665	4+672.5	R										7.5													
S1		4+600	4+668.5	R																			6.0	68.5	1		
S2		4+668.5	4+672	R																			4.0		1		
S3		4+689.5		L																1							
R1		4+600	4+621.3	R	21.3	1																					
R2		4+621.3	4+672	R	50.7																						
R3		4+648	4+649.5	L&R	24		1																				
R4		4+649		R				1																			
U1-U6		4+600	4+700	L&R					12																182		
TOTALS CARRIED TO SHEET 58A					266.0	2	7	2	30	3	47.5	87.2	23.7	53.3	79.3	40	6		2	2	3	2	360.9	10.0	168.5	3	1

ESTIMATED QUANTITIES - STA. 4+500 TO 4+700

LAK-640-3.444

85  
214