

REFERENCE NO.	PLAN & PROFILE SHEET NO.	STATION		SIDE	STORM															SANITARY							
					202				603					604				605	603			604					
					PIPE REMOVED 600 mm AND UNDER	MANHOLE REMOVED	CATCH BASIN REMOVED	INLET BASIN REMOVED	150 mm CONDUIT, TYPE F (*)	300 mm CONDUIT, TYPE B, AS PER PLAN	300 mm CONDUIT, TYPE C, AS PER PLAN	375 mm CONDUIT, TYPE B, AS PER PLAN	525 mm CONDUIT, TYPE B, AS PER PLAN	675 mm CONDUIT, TYPE B, AS PER PLAN (62.5 D-LOAD)	CATCH BASIN NO. 3 AS PER PLAN	CATCH BASIN NO. 3A AS PER PLAN	MANHOLE NO. 3 AS PER PLAN	MANHOLE NO. 3 TYPE A AS PER PLAN	MANHOLE ADJUSTED TO GRADE	MANHOLE RECONSTRUCTED TO GRADE	150 mm SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP	300 mm CONDUIT TYPE B	300 mm CONDUIT, TYPE B 748.01, ANSI CLASS 53 AS PER PLAN	375 mm CONDUIT TYPE B AS PER PLAN	400 mm CONDUIT, TYPE B 748.01, ANSI CLASS 53 AS PER PLAN	MANHOLE NO.3 AS PER PLAN	
METER	EACH	EACH	EACH	METER	METER	METER	METER	METER	METER	EACH	EACH	EACH	EACH	EACH	EACH	METER	METER	METER	METER	METER	EACH						
D1	86			R																1							
D2		4+740		L&R					18.2																		
D3		4+740		R							25.0																
S1		4+710.5		R																							
S2		4+798.5		L																							
R1		4+709	4+711.5	R	3.5																						
R2		4+709	4+711.5	L&R	17																						
R3		4+770		L&R	19																						
U1-U4		4+700	4+800	L&R					6																		
D1	87	4+801.5	4+818.5	R										23.9			1										
D2		4+801.5	4+814.75	R						2.4				13.2				1									
D3		4+809		R																							
D4		4+808.2	4+814.75	R						8.8							1										
D5		4+814.75	4+819.5	R						7.5							1										
D6		4+818.5	4+825	Q&R									11.1				1	1									
D7		4+819.5	4+825	Q&L						9.6							1										
D8		4+818.5	4+860	R										41.5			1										
D9		4+834		L&R						7.2																	
D10		4+849	4+860	R						11.3																	
D11		4+860	4+871	L&R						17.5							1										
D12		4+860	4+900	L&R							8.0			40			1										
S1		4+808.75	4+804.75	R																			8.3				
S2		4+814.75		R																			4.5				
S3		4+804.74	4+827	Q&L																		2.4		12.7			
S4		4+856.7		L																				1			
R1		4+810	4+818	R	26.5		2																				
R2		4+819	4+834	R	15.4																						
R3		4+834		L																							
R4		4+835.5		R		1																					
R5		4+863	4+900	L	41																						
U1-U10		4+800	4+900	L&R					21															203.6			
TOTALS CARRIED TO SHEET 58A					122.4	1	2	6		27	82.5	33	11.1	13.2	105.4		7	4	2	3	3	394.6	2.4	4.5	8.3	12.7	1

ESTIMATED QUANTITIES - STA. 4+700 TO 4+900

LAK-640-3.444