

GENERAL SUMMARY

LAKE COUNTY LAK-84-17.20	OHIO FHWA REGION 5 FEDERAL PROJECT
-----------------------------	--

13 53

PLOTTED BY: lennon
 PLOTTED FROM: c:\dgn\p\d05662\05662gga.dgn
 05662GGC.dgn
 000
 04
 2-
 PLOT SUBMITTED: 12-NOV-1992 10:19

ITEM	SHEET NUMBER		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN SHEET REF.
	44	45						
							TRAFFIC CONTROL	
625			625	25102	17	LIN.FT.	CONDUIT, 1', 713.07, TYPE DB	
625			625	25402	107	LIN.FT.	CONDUIT, 2', 713.07, TYPE DB	
625			625	25802	5	LIN.FT.	CONDUIT, CONCRETE ENCASED, 4', 713.07, TYPE EB	
625			625	29000	129	LIN.FT.	TRENCH	
625			625	30700	2	EACH	PULL BOX, 713.08, 18"	
625			625	32000	3	EACH	GROUND ROD	
630			630	03100	91	LIN.FT.	GROUND MOUNTED SUPPORT, NO. 3 POST	
630			630	80100	29	SQ.FT.	SIGN, FLAT SHEET	
630			630	85000	7	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	
630			630	86006	7	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND STORAGE	
632			632	00301	7	EACH	VEHICULAR SIGNAL HEAD, 3-SECTION, 12" LENS, 1 WAY, AS PER PLAN	43
632			632	00501	1	EACH	VEHICULAR SIGNAL HEAD, 5-SECTION, 12" LENS, 1 WAY, AS PER PLAN	43
632			632	25000	8	EACH	COVERING OF VEHICULAR SIGNAL HEAD	
632			632	27009	4	EACH	LOOP DETECTOR UNIT, DELAY AND EXTENSION TYPE, AS PER PLAN	43
632			632	27500	396	LIN.FT.	LOOP DETECTOR PAVEMENT CUTTING	
632			632	29900	145	LIN.FT.	MESSENGER WIRE, 7-STRAND, 1/4" DIAMETER WITH ACCESSORIES	
632			632	30200	86	LIN.FT.	MESSENGER WIRE, 7-STRAND, 3/8" DIAMETER WITH ACCESSORIES	
632			632	40700	475	LIN.FT.	SIGNAL CABLE, 7-CONDUCTOR NO. 14 AWG	
632			632	64900	820	LIN.FT.	LOOP DETECTOR WIRE, TYPE E	
632			632	65200	127	LIN.FT.	LOOP DETECTOR LEAD IN CABLE	
632			632	67200	152	LIN.FT.	POWER CABLE, 2-CONDUCTOR, NO. 8 AWG	
632			632	70000	1	EACH	POWER SERVICE	
632			632	70200	1	EACH	CONDUIT RISER, 1" DIAMETER	
632			632	71000	3	EACH	CABLE SUPPORT ASSEMBLY	
632			632	72000	4.8	CU.YD.	CONCRETE FOR ANCHOR BASE FOUNDATION	
632			632	82500	2	EACH	STRAIN POLE, TYPE TC 81.10, DESIGN NO. 5	
633			633	33201	1	EACH	CONTROLLER, ACTUATED, 3-PHASE, EXPANSIBLE TO 4-PHASE, SOLID STATE DIGITAL MICROPROCESSOR, AS PER PLAN	43
633			633	70000	1	CU.YD.	CONCRETE FOR CABINET FOUNDATION	
633			633	70500	8.3	SQ.FT.	CONTROLLER WORK PAD	
642			642	00102	0.42	MILES	EDGE LINE, TYPE 2	
642			642	00302	0.38	MILES	CENTER LINE, TYPE 2	
642			642	00402	197	LIN.FT.	CHANNELIZING LINE, TYPE 2	
642			642	00502	115	LIN.FT.	STOP LINE, TYPE 2	
642			642	00702	123	LIN.FT.	TRANSVERSE LINE, TYPE 2	
642			642	01302	3	EACH	LANE ARROW, TYPE 2	
642			642	01402	2	EACH	WORD ON PAVEMENT, 72", TYPE 2	
642			642	01502	141	LIN.FT.	DOTTED LINE, 4", TYPE 2	
614			614	11000	LUMP		MAINTAINING TRAFFIC	
619			619	15010	LUMP		FIELD OFFICE, TYPE B	
623			623	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
624			624	10000	LUMP		MOBILIZATION	