



EXCAVATION INCLUDED IN LUMP SUM PRICE FOR ITEM 615, TEMPORARY ROADS. BACKFILL AFTER TEMPORARY S.R. 84 IS ABANDONED, PAYMENT INCLUDED IN LUMP SUM PRICE FOR ITEM 615, TEMPORARY ROADS.

EXCAVATION FOR TEMPORARY ROAD INCLUDED IN LUMP SUM PRICE FOR ITEM 615, TEMPORARY ROADS.

REMOVE TEMPORARY ROAD EMBANKMENT AFTER TEMPORARY S.R. 84 IS ABANDONED. PAYMENT INCLUDED IN LUMP SUM PRICE FOR ITEM 615, TEMPORARY ROADS.

END STA	AREA		VOLUME	
	CUT	FILL	CUT	FILL
99		9		
90		0	175	9
81		9	159	9
63		9	134	17
			109	17

EXCAVATION 1378 C.Y.
 EMBANKMENT 170 C.Y.

STATE ROUTE 84