

SHEET NUMBER											ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
5	6	7	8	10	11	13	14									
										987.5	202	38000	987.5	LIN.FT.	GUARDRAIL REMOVED	
	120										202	54101	120	EACH	RAISED PAVEMENT MARKERS REMOVED FOR STORAGE, AS PER PLAN	5
										700	203	12000	700	CU.YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
	200										203	60000	213	STA.	LINEAR GRADING	
	350										251	01000	250	SQ.YD.	PARTIAL DEPTH PAVEMENT REPAIR	
	1250										253	01000	950	SQ.YD.	PAVEMENT REPAIR	
										25363	254	01001	25363	SQ.YD.	PAVEMENT PLANING, BITUMINOUS, AS PER PLAN, 1"	5
										11307	254	01001	11307	SQ.YD.	PAVEMENT PLANING, BITUMINOUS, AS PER PLAN, 2"	5
			3700								254	01600	3700	SQ.YD.	PATCHING PLANED SURFACE	
										700	301	46000	700	CU.YD.	BITUMINOUS AGGREGATE BASE, PG64-22	
										3667	407	10000	3667	GALLON	TACK COAT	
										1834	407	14000	1834	GALLON	TACK COAT FOR INTERMEDIATE COURSE	
										511	448	46020	511	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG64-22	
											448	46060	47.3	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG 64-22 (UNDER GUARDRAIL)	
											448	47000	1529	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG76-22	
						45					448	48020	45	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG64-22(DRIVEWAYS)	
				12							604	09001	12	EACH	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN	7
				3							604	09500	3	EACH	CATCH BASIN RECONSTRUCTED TO GRADE	
				2							604	34501	2	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	7
				2							604	35500	2	EACH	MANHOLE RECONSTRUCTED TO GRADE	
				2							604	39501	2	EACH	MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	7
				1							604	39600	1	EACH	MONUMENT BOX RECONSTRUCTED TO GRADE	
				1000							SPECIAL	60450000	1000	POUND	MISCELLANEOUS METAL	7
										1150	606	13000	1150	LIN.FT.	GUARDRAIL, TYPE 5	
										5	606	25000	5	EACH	ANCHOR ASSEMBLY, TYPE A	
										8	614	12460	8	EACH	WORK ZONE MARKING SIGN	
										75	614	13000	75	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
										4.86	614	21100	4.86	MILE	TEMPORARY CENTER LINE, CLASS I, 642 PAINT	
										2.43	614	21500	2.43	MILE	TEMPORARY CENTER LINE, CLASS II, 642 PAINT	
										9.72	614	22100	9.72	MILE	TEMPORARY EDGE LINE, CLASS I, 642 PAINT	
										250	614	26200	250	LIN.FT.	TEMPORARY STOP BAR, CLASS I, 642 PAINT	
										370	617	10100	300	CU.YD.	COMPACTED AGGREGATE, TYPE A	
										208	621	00200	208	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY	11
											14	626	00300	EACH	BARRIER REFLECTOR, TYPE A2	
											3	638	65400	EACH	VALVE ADJUSTED TO GRADE, AS PER PLAN	7
										4.86	828	10000	4.86	MILE	EDGELINE	
										2.43	828	10200	2.43	MILE	CENTERLINE	
										125	828	10400	125	LIN.FT.	STOP LINE	
										2	828	20100	2	EACH	SCHOOL SYMBOL MARKING, 72"	
											614	11000		LUMP	MAINTAINING TRAFFIC	
											623	10000		LUMP	CONSTRUCTION LAYOUT STAKES	
											624	10000		LUMP	MOBILIZATION	

PLOTTED FROM: I:\PROJECTS\1505\21505\21505.dgn

GENERAL SUMMARY

LAKE COUNTY  
LAK-84-19.11