SCOPE OF PROJECT

THE WORK PROPOSED FOR THIS PROJECT CONSISTS OF REPAIRING AND RESURFACING THE EXISTING PAVEMENT USING PARTIAL DEPTH PAVEMENT REPAIRS, HEATER RECYCLING, AND AN ASPHALT CONCRETE OVERLAY.

THE ALIGNMENT OF THE EXISTING PAVEMENT WILL NOT BE CHANGED. THE PROFILE OF THE PROPOSED SURFACE WILL BE SIMILAR TO THAT OF THE EXISTING PAVEMENT EXCEPT THAT IT WILL BE RAISED AN AMOUNT EQUAL TO THE THICKNESS OF THE RESURFACING COURSE SPECIFIED IN THE PLANS.

UTILITIES OWNERSHIP

THE FOLLOWING UTILITIES AND OWNERS ARE LOCATED WITHIN THE WORK LIMITS OF THE PROJECT. THE OHIO DEPARTMENT OF TRANSPORTATION HAS USED THE BEST AVAILABLE INFORMATION TO DETERMINE THE UTILITY COMPANIES SERVING THIS AREA, BUT CANNOT GUARANTEE THE UTILITY COMPANY LIST IS COMPLETE.

EAST OHIO GAS
1201 EAST 55th STREET
CLEVELAND, OHIO 44103
ATTN: PAUL ARENDASH
(216) 736-6675
FAX: 736-6780

CLEVELAND ELECTRIC ILLUMINATING CO. EAST 7755 AUBURN RD. PAINESVILLE, OHIO 44077 ATTN: RICH KERNEY, PHILLIP MULLET (440) 953-7751 953-7741 FAX: 953-7750

AMERITECH
13630 LORAIN AVE. - 4th FLOOR
CLEVELAND, OHIO 44111
ATTN: SHELLEY ARMSTRONG
(216) 476-6142 FAX: 476-6142

AMERICAN TELEPHONE & TELEGRAPH c/o BYERS ENGINEERING COMPANY 3972-D BROWN PARK DRIVE HILLIARD, OHIO 43026-1167 ATTN: TONY LYLE (614) 876-7300 FAX: 476-6013 LAKE CO. DEPT. OF UTILITIES
LAKE CO. WATER
ADMINISTRATION BUILDING
105 MAIN STREET
PAINESVILLE, OHIO 44077
ATTN: ALBERT SAARI
(440) 664-3247

CITY OF PAINESVILLE
P.O. BOX 601
PAINESVILLE, OHIO 44077
ELECTRIC - THOMAS GREEN
(440) 352-9301 FAX: 357-1966
WATER - WILLIAM VARGYARS
(440) 352-9301 FAX: 639-4998

US SPRINT COMMUNICATIONS CO. MIDWEST DIVISION 2650 BROADWAY CLEVELAND, OHIO 44115 ATTN: TOM WRIGHT (216) 781-4443 FAX: 781-4443

WESTERN RESERVE TELEPHONE (ALLTEL)
245 NORTH MAIN ST.
HUDSÖN, OHIO 44236
ATTN: DICK KREJCI
(330) 656-8519 FAX: 656-2929

COOPERATION BETWEEN CONTRACTORS

THE CONTRACTOR SHALL COOPERATE AND COORDINATE HIS OPERATIONS WITH THE CONTRACTORS ON OTHER PROJECTS THAT MAY BE IN FORCE DURING THE LIFE OF THE CONTRACT. NO WAIVER OF ANY PROVISIONS OF 105.07 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS IS INTENDED.

CONTINGENCY QUANTITIES

THE CONTRACTOR SHALL NOT ORDER MATERIAL OR PERFORM WORK FOR THE PLAN ITEMS SET UP TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER.

EXISTING TYPICAL SECTIONS

EXISTING TYPICAL SECTIONS HAVE BEEN TAKEN FROM THE RECORDS AND ARE BELIEVED TO REPRESENT THE EXISTING PAVEMENT CONDITIONS, BUT THE STATE OF OHIO WILL NOT GUARANTEE THE ACCURACY OF THE SAME.

RIGHT OF WAY

ALL WORK IS TO BE PERFORMED WITHIN THE EXISTING RIGHT OF WAY.

ITEM 254-PAVEMENT PLANING, BITUMINOUS

THIS ITEM SHALL CONSIST OF REMOVING THE ASPHALT OVERLAY AND WEDGE NECESSARY FOR THE BUTT JOINTS (SEE STANDARD DRAWING BP-3.IM).