

SHEET NUMBER											ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	7	8	9	10	11	13	15	16	17						
										3750	202	38000	3750	LIN.FT.	GUARDRAIL REMOVED	
431											202	54101	431	EACH	RAISED PAVEMENT MARKERS REMOVED FOR STORAGE, AS PER PLAN	
300				75							203	11000	75	CU.YD.	EXCAVATION INCLUDING EMBANKMENT CONSTRUCTION	
				6						70	203	60000	376	STA.	LINEAR GRADING	4
1500											251	01000	1500	SQ.YD.	PARTIAL DEPTH PAVEMENT REPAIR	
									1011		254	01000	1011	SQ.YD.	PAVEMENT PLANING, BITUMINOUS	3
											103595	SPECIAL 40465000	103595	SQ.YD.	ASPHALT CONCRETE PAVEMENT SURFACE HEATER RECYCLING	6-7
											10359	SPECIAL 40466000	10359	GALLON	ASPHALT REJUVENATING AGENT	6-7
											10543	407 10000	10543	GALLON	TACK COAT	4
											3021	448 47020	3021	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22	
										260	448	46060	260	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG 64-22 (UNDER GUARDRAIL)	8
									51		448	48020	51	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22 (DRIVEWAYS)	4
											604	09001	6	EACH	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN	
											604	34501	6	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	
											604	39501	2	EACH	MONUMENT ADJUSTED TO GRADE, AS PER PLAN	
500											SPECIAL 60450000	500	POUND	MISCELLANEOUS METAL	5	
										5700	606	13000	5700	LIN.FT.	GUARDRAIL, TYPE 5	14
										28	606	22010	28	EACH	ANCHOR ASSEMBLY, TYPE E-98	
										38	614	12460	38	EACH	WORK ZONE MARKING SIGN	
75											614	13000	75	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
											614	21100	6.73	MILE	TEMPORARY CENTER LINE, CLASS I, 642 PAINT	
											614	21500	6.73	MILE	TEMPORARY CENTER LINE, CLASS II, 642 PAINT	
											614	26200	400	LIN.FT.	TEMPORARY STOP LINE CLASS I, 642 PAINT	
271											617	10101	271	CU.YD.	COMPACTED AGGREGATE, TYPE A, AS PER PLAN	5
										431	621	00201	431	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY, AS PER PLAN	10
											632	26500	3	EACH	DETECTOR LOOP	
											642	00102	13.46	MILE	EDGELINE, TYPE 2	
											642	00302	6.73	MILE	CENTERLINE, TYPE 2	5
											644	00500	216	LIN.FT.	STOP LINE	
											7897	10000	7897	SQ.YD.	SEEDING AND MULCHING	
										9	659	20000	1	TON	COMMERCIAL FERTILIZER	
				9							SPECIAL 69050000	9	EACH	MAILBOX SUPPORT		
										350	830	10000	350	LIN.FT.	ASPHALT CONCRETE CURB, TYPE 1	
											614	11000		LUMP	MAINTAINING TRAFFIC	
											623	10000		LUMP	CONSTRUCTION LAYOUT STAKES	
											624	10000		LUMP	MOBILIZATION	

GENERAL SUMMARY

LAK-84-21.54

I:\PROJECTS\PI\17997\17997.gga.dgn 01-NOV-1999 9:15AM jgr mov se